



KERR-McGEE OIL & GAS ONSHORE LP
1999 BROADWAY, SUITE 3700 • DENVER, COLORADO 80202

PHONE: 303-296-3600
FAX: 303-296-3601

June 20, 2006

Ms. Diana Whitney
Division of Oil, Gas and Mining
P.O. Box 145801
Salt Lake City, UT 84114-6100

RE: Bonanza 1023-8H
T10S-R23E
Section 8: SENE
2,619' FNL, 799' FEL
Uintah County, Utah

Dear Ms. Whitney:

Kerr-McGee Oil & Gas Onshore LP has submitted a permit to drill the captioned well to test the Wasatch and Mesaverde formations. The well is located at an exception location to State Rule 179-12. The well location is less than 920' from the proposed Bonanza 1023-8I well. Both wells are located within the same E/2 spacing unit and the proximity between wells does not interfere with the correlative rights of the royalty and working interest owners.

Kerr-McGee requests your approval of this exception location. If you have any questions or require any additional information, please do not hesitate to call me at 720-264-2618.

Sincerely,

W. Chris Latimer, CPL
Senior Landman

cc: Raleen Weddle

RECEIVED

JUL 03 2006

DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

FORM APPROVED
OMB No. 1004-0136
Expires November 30, 2000

1a. Type of Work: ☒ DRILL ☐ REENTER

b. Type of Well: ☐ Oil Well ☒ Gas Well ☐ Other ☐ Single Zone ☒ Multiple Zone

2. Name of Operator

KERR MCGEE OIL & GAS ONSHORE LP

3A. Address

1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-7024

4. Location of Well (Report location clearly and in accordance with any State requirements. *)

At surface

SENE 2619'FNL, 799'FEL 641478X

39.163583

At proposed prod. Zone

4424'19.1

-109.343332

14. Distance in miles and direction from nearest town or post office*

27.35 MILES SOUTHEAST OF OURAY, UTAH

15. Distance from proposed*
location to nearest
property or lease line, ft.
(Also to nearest drig. unit line, if any)

799'

16. No. of Acres in lease

1920.00

17. Spacing Unit dedicated to this well

40.00

18. Distance from proposed location*
to nearest well, drilling, completed,
applied for, on this lease, ft.

REFER TO
TOPO C

19. Proposed Depth

8020'

20. BLM/BIA Bond No. on file

BOND NO. 2971100-2533

21. Elevations (Show whether DF, KDB, RT, GL, etc.)

5285'GL

22. Approximate date work will start*

23. Estimated duration

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office.

4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification.
6. Such other site specific information and/or plans as may be required by the authorized office.

25. Signature

Title

REGULATORY ANALYST

Approved by Signature

Title

Name (Printed/Typed)

SHEILA UPCHEGO

Date

6/1/2006

Name (Printed/Typed)

BRADLEY G. HILL
ENVIRONMENTAL MANAGER

Date

07-10-06

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.


Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on reverse)

Federal Approval of this
Application

JUN 05 2006

T10S, R23E, S.L.B.&M.



Kerr-McGee Oil & Gas Onshore LP


Well location, BONANZA #1023-8H, located as shown in the SE 1/4 NE 1/4 of Section 8, T10S, R23E, S.L.B.&M. Uintah County, Utah.

BASIS OF ELEVATION

BENCH MARK (58 EAM) LOCATED IN THE NE 1/4 OF SECTION 30, T9S, R23E, S.L.B.&M. TAKEN FROM THE RED WASH SE, QUADRANGLE, UTAH, UINTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5132 FEET.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

Robert L. Kay
REGISTERED LAND SURVEYOR
REGISTRATION NO. 161319
STATE OF UTAH

LEGEND:

└─┘ = 90° SYMBOL

● = PROPOSED WELL HEAD.

▲ = SECTION CORNERS LOCATED.

(NAD 83)
LATITUDE = 39°57'48.73" (39.963536)
LONGITUDE = 109°20'38.86" (109.344128)
(NAD 27)
LATITUDE = 39°57'48.85" (39.963569)
LONGITUDE = 109°20'36.42" (109.343450)

UINTAH ENGINEERING & LAND SURVEYING
85 SOUTH 200 EAST - VERNAL, UTAH 84078
(435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 02-17-06	DATE DRAWN: 02-22-06
PARTY J.R. L.M. P.M.	REFERENCES G.L.O. PLAT	
WEATHER COLD	FILE Kerr-McGee Oil & Gas Onshore LP	

**BONANZA #1023-8H
SE/NE Sec. 8, T10S,R23E
UINTAH COUNTY, UTAH
UTU-37355**

ONSHORE ORDER NO. 1

DRILLING PROGRAM

1. Estimated Tops of Important Geologic Markers:

<u>Formation</u>	<u>Depth</u>
Uinta	0- Surface
Green River	1106'
Top of Birds Nest Water	1313'
Mahogany	1918'
Wasatch	4019'
Mesaverde	6137'
MVU2	6971'
MVL1	7505'
TD	8020'

2. Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:

<u>Substance</u>	<u>Formation</u>	<u>Depth</u>
Water	Green River	1106'
	Top of Birds Nest Water	1313'
	Mahogany	1918'
	Wasatch	4019'
Gas	Mesaverde	6137'
Gas	MVU2	6971'
Gas	MVL1	7505'
Water	N/A	
Other Minerals	N/A	

3. Pressure Control Equipment (Schematic Attached)

Please refer to the attached Drilling Program.

4. Proposed Casing & Cementing Program:

Please refer to the attached Drilling Program.

5. Drilling Fluids Program:

Please refer to the attached Drilling Program.

6. Evaluation Program:

Please refer to the attached Drilling Program.

7. **Abnormal Conditions:**

Maximum anticipated bottomhole pressure calculated at 8020' TD, approximately equals 4972 psi (calculated at 0.62 psi/foot).

Maximum anticipated surface pressure equals approximately 3208 psi (bottomhole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot).

8. **Anticipated Starting Dates:**

Drilling is planned to commence immediately upon approval of this application.

9. **Variances:**

Please refer to the attached Drilling Program.

10. **Other Information:**

Please refer to the attached Drilling Program.



KERR-McGEE OIL & GAS ONSHORE LP

DRILLING PROGRAM

COMPANY NAME KERR-McGEE OIL & GAS ONSHORE LP DATE June 1, 2006
WELL NAME BONANZA 1023-8H TD 8,020' MD/TVD
FIELD Natural Buttes COUNTY Uintah STATE Utah ELEVATION 5,285' GL KB 5,300'
SURFACE LOCATION SENE SECTION 8, T10S, R23E 2619'FNL, 799'FEL BHL Straight Hole
Latitude: 39.963536 Longitude: 109.344128
OBJECTIVE ZONE(S) Wasatch/Mesaverde
ADDITIONAL INFO Regulatory Agencies: BLM (SURF & MINERALS), UDOGM, Tri-County Health Dept.

GEOLOGICAL			MECHANICAL		
LOGS	FORMATION	DEPTH	HOLE SIZE	CASING SIZE	MUD WEIGHT
		40'		14"	
			12-1/4"	9-5/8", 32.3#, H-40, STC	Air mist
Catch water sample, if possible, from 0 to 4,019'					
	Green River @	1,106'			
	Top of Birds Nest Water @	1,313'			
	Mahogany @	1,918'			
	Preset f/ GL @	1,920' MD			
Note: 12.25" surface hole will usually be drilled ±400' below the bottom of lost circulation zone. Drilled depth may be ±200' of the estimated set depth depending on the actual depth of the loss zone.					
Mud logging program TBD					
Open hole logging program f/ TD - surf csg					
	Wasatch @	4,019'			
	Mverde @	6,137'			
	MVU2 @	6,971'			
	MVL1 @	7,505'			
			7-7/8"	4-1/2", 11.6#, I-80 or equivalent LTC casing	Water/Fresh Water Mud 8.3-11.0 ppg
					Max anticipated Mud required 11.0 ppg
		TD @ 8,020'			



KERR-McGEE OIL & GAS ONSHORE LP DRILLING PROGRAM

CASING PROGRAM

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-40'				2270	1370	254000
SURFACE	9-5/8"	0 to 1920	32.30	H-40	STC	0.80*****	1.52	4.68
						7780	6350	201000
PRODUCTION	4-1/2"	0 to 8020	11.60	I-80	LTC	2.76	1.38	2.48

- 1) Max Anticipated Surf. Press. (MASP) (Surface Casing) = (Pore Pressure at next csg point - (0.22 psi/ft - partial evac gradient x TVD of next csg point))
- 2) MASP (Prod Casing) = Pore Pressure at TD - (.22 psi/ft - partial evac gradient x TD)
- (Burst Assumptions: TD = 11.0 ppg) .22 psi/ft = gradient for partially evac wellbore
- (Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing * Buoy. Fact. of water)
- MASP 2823 psi
- ***** Burst SF is low but csg is much stronger than formation at 2000'. EMW @ 2000' for 2270# is 21.8 ppg or 1.13 psi/ft

CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE Option 1	LEAD	500	Premium cmt + 2% CaCl + .25 pps flocele	215	60%	15.60	1.18
	TOP OUT CMT (1)	200	20 gals sodium silicate + Premium cmt + 2% CaCl + .25 pps flocele	50		15.60	1.18
	TOP OUT CMT (2)	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
SURFACE Option 2	LEAD	1500	NOTE: If well will circulate water to surface, option 2 will be utilized Prem cmt + 16% Gel + 10 pps gilsonite +.25 pps Flocele + 3% salt BWOC	170	35%	11.00	3.82
	TAIL	500	Premium cmt + 2% CaCl + .25 pps flocele	180	35%	15.60	1.18
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
PRODUCTION	LEAD	3,510'	Premium Lite II + 3% KCl + 0.25 pps celloflake + 5 pps gilsonite + 10% gel + 0.5% extender	390	60%	11.00	3.38
	TAIL	4,510'	50/50 Poz/G + 10% salt + 2% gel + .1% R-3	1260	60%	14.30	1.31

*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe.
PRODUCTION	Float shoe, 1 jt, float collar. Centralize first 3 joints & every third joint to top of tail cement with bow spring centralizers.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. Test to 5,000 psi (annular to 2,500 psi) prior to drilling out. Record on chart recorder & tour sheet. Function test rams on each trip. Maintain safety valve & inside BOP on rig floor at all times. Kelly to be equipped with upper & lower kelly valves.

Drop Totco surveys every 2000'. Maximum allowable hole angle is 5 degrees.

Most rigs have PVT Systems for mud monitoring. If no PVT is available, visual monitoring will be utilized.



DRILLING ENGINEER: _____
 Brad Laney

DRILLING SUPERINTENDENT: _____
 Randy Bayne

DATE: _____

DATE: _____

5M BOP STACK and CHOKE MANIFOLD SYSTEM



**BONANZA 1023-8H
SE/NE SECTION 8, T10S, R23E
UINTAH COUNTY, UTAH
UTU-37355**

ONSHORE ORDER NO. 1

MULTI-POINT SURFACE USE & OPERATIONS PLAN

1. Existing Roads:

Directions to the proposed location are attached.

Refer to Topo Maps A and B for location of access roads within a 2-mile radius.

All existing roads will be maintained and kept in good repair during all drilling and completion operations associated with this well.

2. Planned Access Roads:

Approximately 270' +/- of new access roads is proposed. Refer to Topo Map B.

The access road will be crowned (2 to 3%), ditched and constructed with a running surface of 18 feet and a maximum disturbed width of 30 feet. Graveling or capping the roadbed will be performed as necessary to provide a well constructed, safe road. Prior to construction or upgrading, the proposed road shall be cleared of any snow and allowed to dry completely.

Surface disturbance and vehicular traffic will be limited to the proposed location and proposed access route. Any additional area needed will be approved in advance. All construction shall be in conformance with the standards outlined in the BLM and Forest Service publication: Surface Operating Standards for Oil and Gas Exploration and Development. 1989.

The road surface and shoulders will be kept in a safe and usable condition and will be maintained in accordance with the original construction standards. All drainage ditches will be kept clear and free-flowing and will be maintained according to original construction standards. The access road surface will be kept free of trash during operations. All traffic will be confined to the approved disturbed surface. Road drainage crossings shall be designed so they will not cause siltation or accumulation of debris in the drainage crossing or shall the drainages be blocked by the road bed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means of cutouts. Should mud holes develop, they shall be filled in and detours around them avoided. When snow is removed from the road during the winter months, the snow shall be pushed outside of the borrow ditches, and the turnouts kept clear so that snowmelt will be channeled away from the road.

3. Location of Existing Wells Within a 1-Mile Radius

Please refer to Topo Map C.

4. Location of Existing & Proposed Facilities & Pipelines

The following guidelines will apply if the well is productive.

All production facilities will be located on the disturbed portion of the well pad and at a minimum of 25 feet from the toe of the back slope or the top of the fill slope.

A dike will be constructed completely around those production facilities which contain fluids (i.e., production tanks, produced water tanks, and/or heater/treater). These dikes will be constructed of compacted subsoil, be impervious, hold 100% of the capacity of the largest tank, and be independent of the back cut.

All permanent (on-site six months or longer) above the ground structures constructed or installed, including pumping units, will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the five state Rocky Mountain Inter-Agency Committee.

All facilities will be painted within six months of installation. Facilities required to comply with the Occupational Safety and Health Act (OSHA) will be excluded. The requested color is Carlsbad Canyon (2.5 Y 6/2) as determined during the on-site inspection.

Any necessary pits will be properly fenced to protect livestock and prevent wildlife entry.

Variances to Best Management Practices (BMP) Requests:

Approximately 348' of 4" steel pipeline is proposed. Please refer to the Topo Map D. The pipeline will be butt-welded together.

The pipeline shall be installed on surface within access corridor for the well location. As a Best Management Practice (BMP), the pipeline would be buried within the access road corridor if possible. The construction of pipelines requires the corridor of 30 feet.

This exception to the BMP should be granted by the BLM Authorized Officer because indurated bedrock, such as sandstone, is at or within 2 feet of the surface and the soil has a poor history for successful rehabilitation.

5. Location and Type of Water Supply:

Water for drilling purposes will be obtained from Dalbo Inc.'s underground well located in Ouray, Utah, Sec.32, T4S,R3E, Water User Claim #43-8496, Application #53617.

Water will be hauled to location over the roads marked on Maps A and B.

No water well is to be drilled on this lease.

6. **Source of Construction Materials**

Surface and subsoil materials in the immediate area will be utilized.

Any gravel will be obtained from a commercial source.

7. **Methods of Handling Waste Materials**

Drill cuttings will be contained and buried in the reserve pit.

Drilling fluids, including salts and chemicals, will be contained in the reserve pit. Upon termination of drilling and completion operations, the liquid contents of the reserve pit will be removed and disposed of at an approved waste disposal facility within 120 days after drilling is terminated.

The reserve pit will be constructed on the location and will not be located within natural drainage, where a flood hazard exists or surface runoff will destroy or damage the pit walls. The reserve pit will be constructed so that it will not leak, break, or allow discharge of liquids.

A plastic reinforced liner is to be used as discussed during on-site inspection. It will be a minimum of 20 mil thick and felt with sufficient bedding used to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash or scrap that could puncture the liner will be disposed of in the pit.

Any spills of oil, gas, salt water, or other noxious fluids will be immediately cleaned up and removed to an approved disposal site.

A chemical porta-toilet will be furnished with the drilling rig.

Garbage, trash, and other waste materials will be collected in a portable, self-contained, fully enclosed trash cage during operations. No trash will be burned on location.

All debris and other waste material not contained in the trash cage will be cleaned up and removed from the location immediately after removal of the drilling rig.

Any open pits will be fenced during the operations. The fencing will be maintained until such time as the pits are backfilled.

No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.

Any produced water from the proposed well will be contained in a water tank and will then be hauled by truck to one of the pre-approved disposal sites: RNI, Sec. 5, T9S, R22E, NBU #159, Sec.35, T9S, R21E, Ace Oilfield, Sec. 2, T6S, R20E, MC&MC, Sec. 12, T6S, R19E. (Request is in lieu of filing Form 3160-5, after initial production).

8. Ancillary Facilities

None are anticipated.

9. Well Site Layout: (See Location Layout Diagram)

The attached Location Layout Diagram describes drill pad cross-sections, cuts and fills, and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile(s), and surface material stockpile(s).

Please see the attached diagram to describe rig orientation, parking areas, and access roads.

39 inch net wire will be used with at least one strand of barbed wire on top of the net wire. Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.

The net wire shall be no more than two inches above the ground. The barbed wire shall be three inches over the net wire. Total height of the fence shall be at least 42 inches.

Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.

Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet.

All wire shall be stretched, by using a stretching device, before it is attached to corner posts.

The reserve pit fencing will be on three sides during drilling operations, and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

10. Plans for Reclamation of the Surface:*Producing Location:*

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, materials, trash, and debris not required for production.

Immediately upon well completion, any hydrocarbons in the pit shall be removed in accordance with 43 CFR 3162.7-1.

Before any dirt work associated with location restoration takes place, the reserve pit shall be as dry as possible. All debris in it will be removed. Other waste and spoil materials will be disposed of immediately upon completion of operations.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 90 days from the date of well completion, weather permitting.

To prevent surface water (s) from standing (ponding) on the reclaimed reserve pit area, final reclamation of the reserve pit will consist of "mounding" the surface three feet above surrounding ground surface to allow the reclaimed pit area to drain effectively.

Upon completion of backfilling, leveling, and recontouring, the stockpiled topsoil will be spread evenly over the reclaimed area(s).

Dry Hole/Abandoned Location:

Abandoned well sites, roads, and other disturbed areas will be restored as near as practical to their original condition. Where applicable, these conditions include the re-establishment of irrigation systems, the re-establishment of appropriate soil conditions, and re-establishment of vegetation as specified.

All disturbed surfaces will be recontoured to the approximate natural contours, with reclamation of the well pad and access road to be performed as soon as practical after final abandonment. Reseeding operations will be performed after completion of other reclamation operations.

When the pit is backfilled, the topsoil pile shall be spread on the location up to the rig anchor points. The location will be reshaped to the original contour to the extent possible. The following seed mixture will be used to reclaim the surface for interim reclamation using appropriate reclamation methods. A total of 12 lbs/acre will be used if the seeds are drilled (24 lbs/acre if the seeds are broadcast). The per acre requirements for drilled seeds are:

Crested Wheatgrass	4 lbs.
Needle and Thread Grass	4 lbs
Indian Rice Grass	4 lbs.

The operator shall call BLM for the seed mixture when final reclamation occurs.

11. Surface Ownership:

United States of America
Bureau of Land Management
170 South 500 East
Vernal, UT 84078
(435) 781-4400

12. Other Information:

A Class III Archaeological Report has been performed and completed on May 19, 2005, the Archaeological Report No. 05-91
Paleontological Reconnaissance Report has been performed and completed on May 26, 2006, the Paleontological Report No. 06-89.

WILDLIFE STIPULATIONS:

GOLDEN EAGLE: No construction or drilling from February 1st – July 15th. Submit a letter to BLM to requests a stipulation waiver.

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, the approved Plan of Operations, and any applicable Notice of

Lessees. The Operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the field representative to ensure compliance. The Operator will control noxious weeds along Rights-Of-Way for roads, pipelines, well sites, or other applicable facilities.

13. Lessee's or Operators's Representative & Certification:

Sheila Upchego
Regulatory Analyst
Kerr-McGee Oil & Gas Onshore LP
1368 South 1200 East
Vernal, UT 84078
(435) 781-7024

Randy Bayne
Drilling Manager
Kerr-McGee Oil & Gas Onshore LP
1368 South 1200 East
Vernal, UT 84078
(435)781-7018


Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Kerr-McGee Oil & Gas Onshore LP is considered to be the operator of the subject well. Westport Oil & Gas Company agrees to be responsible under the terms and the conditions of the lease for the operations conducted upon leased lands.

Bond coverage pursuant to 43 CFR 3104 for the lease activities is being provided by BLM Nationwide Bond #2971100-2533.

I hereby certify that the proposed drill site and access route has been inspected and that I am familiar with the conditions that currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed by the Operator, its contractors, and subcontractors in conformity with this plan and the terms and conditions under which it is approved.


Sheila Upchego

June 1, 2006

Date

Kerr-McGee Oil & Gas Onshore LP
BONANZA #1023-8H
SECTION 8, T10S, R23E, S.L.B.&M.

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 14.0 MILES TO THE JUNCTION OF STATE HIGHWAY 88; EXIT LEFT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 17.0 MILES TO OURAY, UTAH; PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 0.3 MILES ON THE SEEP RIDGE ROAD TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 12.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTH; TURN RIGHT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 1.7 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 1.9 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN RIGHT AND PROCEED IN A SOUTHEASTERLY DIRECTION APPROXIMATELY 0.5 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY, THEN SOUTHEASTERLY DIRECTION APPROXIMATELY 3.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHWEST; TURN RIGHT AND PROCEED IN A SOUTHWESTERLY DIRECTION APPROXIMATELY 0.7 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN LEFT AND PROCEED IN A SOUTHEASTERLY, THEN SOUTHERLY DIRECTION APPROXIMATELY 1.9 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTH; TURN RIGHT AND PROCEED IN A SOUTHERLY, THEN SOUTHWESTERLY, THEN SOUTHERLY, THEN SOUTHEASTERLY DIRECTION APPROXIMATELY 3.4 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHEAST; TURN LEFT AND PROCEED IN A NORTHEASTERLY DIRECTION APPROXIMATELY 0.5 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN RIGHT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 0.6 MILES TO THE EXISTING #8-4 AND THE BEGINNING OF THE PROPOSED ACCESS FOR THE #1023-8I TO THE NORTHEAST; FOLLOW ROAD FLAGS IN A NORTHEASTERLY DIRECTION APPROXIMATELY 0.25 MILES TO THE BEGINNING OF THE PROPOSED ACCESS TO THE NORTHEAST; FOLLOW ROAD FLAGS IN A NORTHEASTERLY DIRECTION APPROXIMATELY 270' TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 58.35 MILES.

Kerr-McGee Oil & Gas Onshore LP

BONANZA #1023-8H

LOCATED IN UTAH COUNTY, UTAH

SECTION 8, T10S, R23E, S.L.B.&M.




PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: NORTHWESTERLY



PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS

CAMERA ANGLE: NORTHEASTERLY



UELS Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
435-789-1017 uels@uelsinc.com

LOCATION PHOTOS


02 24 06
MONTH DAY YEAR

PHOTO

TAKEN BY: J.R.

DRAWN BY: C.P.

REVISED: 00-00-00



LEGEND:

○ PROPOSED LOCATION

N

Kerr-McGee Oil & Gas Onshore LP

BONANZA #1023-8H

SECTION 8, T10S, R23E, S.L.B.&M.

2619' FNL 799' FEL



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813



TOPOGRAPHIC
 MAP


02 24 06
 MONTH DAY YEAR

SCALE: 1:100,000

DRAWN BY: C.P.

REVISED: 00-00-00





LEGEND:

————— EXISTING ROAD
 - - - - - PROPOSED ACCESS ROAD

Kerr-McGee Oil & Gas Onshore LP

BONANZA #1023-8H
SECTION 8, T10S, R23E, S.L.B.&M.
2619' FNL 799' FEL



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813




TOPOGRAPHIC
MAP

02 **24** **06**
 MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: C.P. REVISED: 00-00-00

B
TOPO



LEGEND:

- DISPOSAL WELLS
- PRODUCING WELLS
- SHUT IN WELLS
- WATER WELLS
- ABANDONED WELLS
- TEMPORARILY ABANDONED

Kerr-McGee Oil & Gas Onshore LP

BONANZA #1023-8H
SECTION 8, T10S, R23E, S.L.B.&M.
2619' FNL 799' FEL




Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

**TOPOGRAPHIC
MAP**

02 24 06
 MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: C.P. REVISED: 00-00-00

**C
TOPO**



APPROXIMATE TOTAL PIPELINE DISTANCE = 348' +/-

LEGEND:

	PROPOSED ACCESS ROAD
	EXISTING PIPELINE
	PROPOSED PIPELINE
	PROPOSED PIPELINE (SERVICING OTHER WELLS)

N

Kerr-McGee Oil & Gas Onshore LP

BONANZA #1023-8H

SECTION 8, T10S, R23E, S.L.B.&M.

2619' FNL 799' FEL



Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC
MAP

02	24	06
MONTH	DAY	YEAR

SCALE: 1" = 1000' DRAWN BY: C.P. REVISED: 00-00-00

D
TOPO

Kerr-McGee Oil & Gas Onshore LP
BONANZA #1023-8H
PIPELINE ALIGNMENT
LOCATED IN UTAH COUNTY, UTAH
SECTION 8, T10S, R23E, S.L.B.&M.




PHOTO: VIEW FROM TIE-IN POINT

CAMERA ANGLE: NORTHEASTERLY



PHOTO: VIEW OF PIPELINE ALIGNMENT

CAMERA ANGLE: NORTHEASTERLY



- Since 1964 -

UELS Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
435-789-1017 uels@uelsinc.com

PIPELINE PHOTOS

02 24 06
MONTH DAY YEAR

PHOTO

TAKEN BY: J.R.

DRAWN BY: C.P.

REVISED: 00-00-00

FIGURE #1

BONANZA #1023-8H
SECTION 8, T10S, R23E, S.L.B.&M.

C-4.5', 2619' FNL 799' FEL
El. 86.8'

Proposed Access
Road

Approx.
Toe of
Fill Slope

F-10.4'
El. 71.9'

SCALE: 1" = 50'
DATE: 02-22-06
Drawn By: P.M.

NOTE:

Flare Pit is to be located
a min. of 100' from the
Well Head.

Approx.
Top of —
Cut Slope

Topsoil Stockpile

FLARE PIT

Pit Topsoil

C-6.2'
El. 88.5'

Bogie Line

D

C

El. 88.0'
C-15.7'
(btm. pit)

Reserve Pit Backfill
& Spoils Stockpile

100'

150'

RESERVE PITS
(10' Deep)

Total Pit Capacity
W/2' of Freeboard
= 15,490 Bbls. ±
Total Pit Volume
= 4,280 Cu. Yds.

1 1/2:1 Slope

B

El. 86.1'
C-13.8'
(btm. pit)

15' WIDE BENCH/DIKE

RESERVE PITS
(10' Deep)

Total Pit Capacity
W/2' of Freeboard
= 15,490 Bbls. \pm
Total Pit Volume
= 4,280 Cu. Yds.

PIPE TUBS

PIPE RACKS

$F-0.9'$
El. 81.4'

Sta. 3+50

*Round Corners
as Needed*

200'

PIPE TUBS

CATWALK

C-2.6
El. 84.9'

RIG ☐

135' Sta. 1+50

TOILET ☐

F-4.1'
El. 78.2'

LIGHT PLANT

BOILER

COMPRESSOR

11

BOOSTER

Sta. 0+50

F-0.2'
El. 82.1'

A

$F-2.6'$
 $Fl\ 70.7'$

Sta. 0+00

$F-1.2'$
 $FL\ 81.1'$

F-4.2'
FL 78.1'

NOTES:

Elev. Ungraded Ground At Loc. Stake = 5284.9'
FINISHED GRADE ELEV. AT LOC. STAKE = 5282.3'

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

Kerr-McGee Oil & Gas Onshore LP

FIGURE #2

TYPICAL CROSS SECTIONS FOR

BONANZA #1023-8H

SECTION 8, T10S, R23E, S.L.B.&M.

2619' FNL 799' FEL

1" = 20'
X-Section
Scale
1" = 50'

DATE: 02-22-06
Drawn By: P.M.

Preconstruction
Grade

58'

135'

Finished Grade

CUT

FILL

STA. 3+50

15'
BENCH

100'

58'

135'

Location Stake

CUT

FILL

STA. 1+50

15'
BENCH

100'

58'

135'

Slope = 1 1/2:1
(Typ.)

CUT

FILL

STA. 0+50

15'
BENCH

173'

135'

CUT

FILL

STA. 0+00

NOTE:

Topsoil should not be
Stripped Below Finished
Grade on Substructure Area.

* NOTE:

FILL QUANTITY INCLUDES
5% FOR COMPACTION

APPROXIMATE YARDAGES

CUT

(6") Topsoil Stripping = 1,940 Cu. Yds.
Remaining Location = 10,500 Cu. Yds.

TOTAL CUT = 12,440 CU.YDS.

FILL = 8,360 CU.YDS.

EXCESS MATERIAL = 4,080 Cu. Yds.

Topsoil & Pit Backfill = 4,080 Cu. Yds.
(1/2 Pit Vol.)

EXCESS UNBALANCE = 0 Cu. Yds.
(After Rehabilitation)

UINTAH ENGINEERING & LAND SURVEYING

85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 06/05/2006

API NO. ASSIGNED: 43-047-38222

WELL NAME: BONANZA 1023-8H

OPERATOR: KERR-MCGEE OIL & GAS (N2995)

CONTACT: SHEILA UPCHEGO

PHONE NUMBER: 435-781-7024

PROPOSED LOCATION:

SENE 08 100S 230E

SURFACE: 2619 FNL 0799 FEL

BOTTOM: 2619 FNL 0799 FEL

COUNTY: UINTAH

LATITUDE: 39.96358 LONGITUDE: -109.3435

UTM SURF EASTINGS: 641478 NORTHINGS: 4424819

FIELD NAME: NATURAL BUTTES (630)

INSPECT LOCATN BY: / /		
Tech Review	Initials	Date
Engineering		
Geology		
Surface		

LEASE TYPE: 1 - Federal

LEASE NUMBER: UTU-37355

SURFACE OWNER: 1 - Federal

PROPOSED FORMATION: WSMVD

COALBED METHANE WELL? NO

RECEIVED AND/OR REVIEWED:

☒ Plat

☒ Bond: Fed[1] Ind[] Sta[] Fee[]
(No. 2971100-2533)

☒ Potash (Y/N)

☒ Oil Shale 190-5 (B) or 190-3 or 190-13

☒ Water Permit
(No. 43-8496)

☒ RDCC Review (Y/N)
(Date:)

☒ Fee Surf Agreement (Y/N)

☒ Intent to Commingle (Y/N)

LOCATION AND SITING:

☐ R649-2-3.

Unit: _____

☐ R649-3-2. General

Siting: 460 From Qtr/Qtr & 920' Between Wells

☒ R649-3-3. Exception

☒ Drilling Unit

Board Cause No: 179-12


Eff Date: 7-5-05

Siting: 460' Fr unit w/drgs & 920' Fr over wells

☐ R649-3-11. Directional Drill

COMMENTS: _____

STIPULATIONS: 1- Federal Approved



OPERATOR: KERR MCGEE O&G (N2995)

SEC: 4,5,8,9,17,18 T. 10S R. 23E

FIELD: NATURAL BUTTES (630)

COUNTY: UTAH

CAUSE: 179-12 / 7-5-2005

Field Status


- ABANDONED
- ACTIVE
- COMBINED
- INACTIVE
- PROPOSED
- STORAGE
- TERMINATED

Unit Status

- EXPLORATORY
- GAS STORAGE
- NF PP OIL
- NF SECONDARY
- PENDING
- PI OIL
- PP GAS
- PP GEOTHERML
- PP OIL
- SECONDARY
- TERMINATED

Wells Status

- GAS INJECTION
- GAS STORAGE
- LOCATION ABANDONED
- NEW LOCATION
- PLUGGED & ABANDONED
- PRODUCING GAS
- PRODUCING OIL
- SHUT-IN GAS
- SHUT-IN OIL
- TEMP. ABANDONED
- TEST WELL
- WATER INJECTION
- WATER SUPPLY
- WATER DISPOSAL
- DRILLING



PREPARED BY: DIANA WHITNEY
DATE: 14-JUNE-2006



State of Utah

**Department of
Natural Resources**

MICHAEL R. STYLER
Executive Director

**Division of
Oil, Gas & Mining**

JOHN R. BAZA
Division Director

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

July 10, 2006

Kerr-McGee Oil & Gas Onshore LP
1368 South 1200 East
Vernal, UT 84078

Re: Bonanza 1023-8H Well, 2619' FNL, 799' FEL, SE NE, Sec. 8, T. 10 South,
R. 23 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

Appropriate information has been submitted to DOGM and administrative approval of the requested exception location is hereby granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-38222.

Sincerely,

A handwritten signature in black ink, appearing to read "Gil Hunt".

Gil Hunt
Associate Director

pab
Enclosures

cc: Uintah County Assessor
Bureau of Land Management, Vernal District Office

Operator: Kerr-McGee Oil & Gas Onshore LP
Well Name & Number Bonanza 1023-8H
API Number: 43-047-38222
Lease: UTU-37355

Location: SE NE **Sec.** 8 **T.** 10 South **R.** 23 East

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

Notify the Division within 24 hours of spudding the well.

- Contact Carol Daniels at (801) 538-5284.

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dan Jarvis at (801) 538-5338

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.

RECEIVED

JUN 01 2006

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0136
Expires November 30, 2000



APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER			5. Lease Serial No. UTU-37355	
b. Type of Well: <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/> Single Zone <input checked="" type="checkbox"/> Multiple Zone			6. If Indian, Allottee or Tribe Name	
2. Name of Operator KERR MCGEE OIL & GAS ONSHORE LP			7. If Unit or CA Agreement, Name and No.	
3A. Address 1368 SOUTH 1200 EAST VERNAL, UT 84078		3b. Phone No. (include area code) (435) 781-7024		
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface SENE 2619'FNL, 799'FEL At proposed prod. Zone			8. Lease Name and Well No. BONANZA 1023-8H	
14. Distance in miles and direction from nearest town or post office* 27.35 MILES SOUTHEAST OF OURAY, UTAH			9. API Well No. 43-047-38222	
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 799'		10. Field and Pool, or Exploratory NATURAL BUTTES		
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. REFER TO TOPO C		11. Sec., T., R., M., or Blk, and Survey or Area SECTION 8, T10S, R23E		
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 5285'GL		16. No. of Acres in lease 1920.00		17. Spacing Unit dedicated to this well 40.00
		19. Proposed Depth 8020'		20. BLM/BIA Bond No. on file BOND NO. 2971100-2533 C01203
		22. Approximate date work will start*		23. Estimated duration

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- | | |
|---|---|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification. |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the authorized office. |

25. Signature 	Name (Printed/Typed) SHEILA UPCHEGO	Date 6/1/2006
Title REGULATORY ANALYST		
Approved by (Signature) 	Name (Printed/Typed) JERRY KEVORKA	Date 2-15-2007
Title Assistant Field Manager Lands & Mineral Resources		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on reverse)

NOTICE OF APPROVAL

RECEIVED

FEB 22 2007

DIV. OF OIL, GAS & MINING


06BM1293A

UD06M



UNITED STATES DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
VERNAL FIELD OFFICE

170 South 500 East VERNAL, UT 84078 (435) 781-4400



CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL

Company:	Kerr-McGee O&G Onshore, LP	Location:	SENE, Sec 8, T10S, R23E
Well No:	Bonanza 1023-8H	Lease No:	UTU-37355
API No:	43-047-38222	Agreement:	N/A

Petroleum Engineer:	Ryan Angus	Office: 435-781-4430	Cell: 435-828-
Petroleum Engineer:	James Ashley	Office: 435-781-4470	Cell: 435-828-7874
Petroleum Engineer:	Matt Baker	Office: 435-781-4490	Cell: 435-828-4470
Petroleum Engineer:	Michael Lee	Office: 435-781-4432	
Supervisory Petroleum Technician:	Jamie Sparger	Office: 435-781-4502	Cell: 435-828-3913
NRS/Environmental Scientist:	Scott Ackerman	Office: 435-781-4437	
NRS/Environmental Scientist:	Paul Buhler	Office: 435-781-4475	Cell: 435-828-4029
NRS/Environmental Scientist:	Jannice Cutler	Office: 435-781-3400	
NRS/Environmental Scientist:	Michael Cutler	Office: 435-781-3401	
NRS/Environmental Scientist:	Anna Figueroa	Office: 435-781-3407	
NRS/Environmental Scientist:	Melissa Hawk	Office: 435-781-4476	
NRS/Environmental Scientist:	Chuck Macdonald	Office: 435-781-4441	
NRS/Environmental Scientist:	Nathan Packer	Office: 435-781-3405	
NRS/Environmental Scientist:	Verlyn Pindell	Office: 435-781-3402	
NRS/Environmental Scientist:	Holly Villa	Office: 435-781-4404	
NRS/Environmental Scientist:	Darren Williams	Office: 435-781-4447	
NRS/Environmental Scientist:	Karl Wright	Office: 435-781-4484	
After Hours Contact Number: 435-781-4513		Fax: 435-781-4410	

**A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR
FIELD REPRESENTATIVE TO INSURE COMPLIANCE**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a one-year period. An additional year extension may be applied for by sundry notice prior to expiration.**

NOTIFICATION REQUIREMENTS

Location Construction (Notify NRS)	-	Forty-Eight (48) hours prior to construction of location and access roads.
Location Completion (Notify NRS)	-	Prior to moving on the drilling rig.
Spud Notice (Notify Petroleum Engineer)	-	Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify Supervisory Petroleum Technician)	-	Twenty-Four (24) hours prior to running casing and cementing all casing
BOP & Related Equipment Tests (Notify Supervisory Petroleum Technician)	-	Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify Petroleum Engineer)	-	Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

***SURFACE USE PROGRAM
CONDITIONS OF APPROVAL (COAs)***

1. If paleontologic materials are uncovered during construction, the operator shall immediately stop work that might further disturb such materials and contact the Authorized Officer (AO). A determination will be made by the AO as to what mitigation will be necessary for the discovered paleontologic material.
2. The topsoil from the reserve pit should be stripped and piled separately near the reserve pit. When the reserve pit is closed, it shall be re-contoured and the topsoil re-spread, and the area shall be seeded in the same manner as the location topsoil.
3. Once the location is plugged and abandoned, it shall be re-contoured to natural contours, topsoil re-spread where appropriate, and the entire location seeded with the recommended seed mix. Seeding should take place by broadcasting the seed and walking it into the soil with a dozer immediately after the dirt work is completed.
4. A timing restriction on construction and drilling (including completion) from February 1 – July 15, is in order to protect nesting Golden Eagles. If it is anticipated that construction or drilling would occur during the given timing restrictions a BLM or qualified biologist shall be notified so surveys could be conducted. Depending upon the results of the survey, permission to proceed may or may not be recommended or granted.

DOWNHOLE CONDITIONS OF APPROVAL

All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to. The following items are emphasized:

SITE SPECIFIC DOWNHOLE CONDITIONS OF APPROVAL

1. Surface casing cement shall be brought up to the surface. To reach the surface, operator is required to pump additional cement beyond the stated amounts of sacks in application.
2. A cement Bond Log (CBL) shall be run from the production casing shoe to the surface casing shoe.

DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS

1. There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well. Any changes in operation must have prior approval from the BLM, Vernal Field Office Petroleum Engineers.
2. The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
3. **Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.**
4. Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.

All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test shall be reported in the driller's log.

BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.

Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.

No aggressive/fresh hard-banded drill pipe shall be used within casing.

5. The lessee/operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled and analyzed (a copy of the analyses to be submitted to the BLM Field Office in Vernal, Utah).

6. All oil and gas shows shall be adequately tested for commercial possibilities, reported, and protected.
7. The lessee/operator must report encounters of all non oil & gas mineral resources (such as gilsonite, tar sands, oil shale, etc.) to a geologist of the Vernal Field Office in writing within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.
8. No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM, Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM, Vernal Field Office shall be obtained and notification given before resumption of operations.
9. Chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.

Any change in the program shall be approved by the BLM, Vernal Field Office. "Sundry Notices and Reports on Wells" (Form BLM 3160-5) shall be filed for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.

Emergency approval may be obtained orally, but such approval does not waive the written report requirement. Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan pursuant to Onshore Oil & Gas Order No. 1 of 43 CFR 3164.1 and prior approval by the BLM, Vernal Field Office.

In accordance with 43 CFR 3162.4-3, this well shall be reported on the "Monthly Report of Operations" (Oil and Gas Operations Report ((OGOR)) starting with the month in which operations commence and continue each month until the well is physically plugged and abandoned. This report shall be filed in duplicate, directly with the Minerals Management Service, P.O. Box 17110, Denver, Colorado 80217-0110, or call 1-800-525-7922 (303) 231-3650 for reporting information.

10. Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if performed. Samples (cuttings, fluid, and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.

A cement bond log (CBL) will be run from the production casing shoe to the surface casing shoe and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.

Please submit an electronic copy of all other logs run on this well in LAS format to UT_VN_Wellogs@BLM.gov. This submission will supersede the requirement for submittal of paper logs to the BLM.

11. All off-lease storage, off-lease measurement, or commingling on-lease or off-lease shall have prior written approval from the BLM, Vernal Field Office.

All measurement points shall be identified as point of sales or allocation for royalty determination prior to the installation of facilities.

12. Oil and gas meters shall be calibrated in place prior to any deliveries. The Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM, Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement.
13. A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM, Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
14. This APD is approved subject to the requirement that, should the well be successfully completed for production, the BLM, Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
 - a. Operator name, address, and telephone number.
 - b. Well name and number.
 - c. Well location (1/4, Sec., Twn, Rng, and P.M.).
 - d. Date well was placed in a producing status (date of first production for which royalty will be paid).
 - e. The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
 - f. The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.

- g. Unit agreement and / or participating area name and number, if applicable.
 - h. Communitization agreement number, if applicable.
15. Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from Field Office Petroleum Engineers.
 16. All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production
 17. Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
 18. Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

5. Lease Serial No.

UTU-37355

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

BONANZA 1023-8H

9. API Well No.

4304738222

10. Field and Pool, or Exploratory Area

NATURAL BUTTES

11. County or Parish, State

UINTAH, UTAH

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

KERR MCGEE OIL AND GAS ONSHORE LP

3a. Address

1368 SOUTH 1200 EAST, VERNAL, UTAH 84078

3b. Phone No. (include area code)

(435)781-7003

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

2619' FNL, 799' FEL

SENE, SEC 8-T10S-R23E

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other APD EXTENSION
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	DOGM
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

THE OPERATOR REQUESTS AUTHORIZATION FOR A ONE YEAR EXTENSION FOR THE SUBJECT WELL LOCATION SO THAT THE DRILLING OPERATIONS MAY BE COMPLETED. THE ORIGINAL APD WAS APPROVED BY THE DIVISION OF OIL, GAS AND MINING ON JULY 10, 2006.

Approved by the
Utah Division of
Oil, Gas and Mining

RECEIVED

JUN 11 2007

Date: 06-20-07

By: [Signature]

DIV. OF OIL, GAS & MINING

6-21-07

RM

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

RAMEY HOOPES

Title

LAND SPECIALIST I

Signature

[Signature: Ramey Hoopes]

Date

June 11, 2007

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**Application for Permit to Drill
Request for Permit Extension
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

API: 4304738222
Well Name: BONANZA 1023-8H
Location: SENE, SEC 8-T10S-R23E
Company Permit Issued to: KERR-MCGEE OIL AND GAS ONSHORE LP
Date Original Permit Issued: 7/10/2006

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes ☐ No ☒

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes ☐ No ☒

Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes ☐ No ☒

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes ☐ No ☒

Has the approved source of water for drilling changed? Yes ☐ No ☒

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes ☐ No ☒

Is bonding still in place, which covers this proposed well? Yes ☒ No ☐

Ramey Hooper
Signature

6/11/2007
Date

Title: LAND SPECIALIST I

Representing: KERR-MCGEE OIL AND GAS ONSHORE L

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: KERR MCGEE OIL & GAS ONSHORE LP Operator Account Number: N 2995
Address: 1368 SOUTH 1200 EAST
city VERNAL
state UT zip 84078 Phone Number: (435) 781-7024

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304737328	BONANZA 1023-4B		NWNE	4	10S	23E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
A	99999	16351	9/15/2007			9/25/07	
Comments: MIRU PETE MARTIN BUCKET RIG. <u>WSMVD</u> SPUD WELL LOCATION ON 09/15/2007 AT 1200 HRS							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304737315	BONANZA 1023-4D		NWNW	4	10S	23E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
A	99999	16352	9/16/2007			9/25/07	
Comments: MIRU PETE MARTIN BUCKET RIG. <u>WSMVD</u> SPUD WELL LOCATION ON 09/16/2007 AT 0900 HRS,							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304738222	BONANZA 1023-8H		SENE	8	10S	23E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
A	99999	16353	9/14/2007			9/25/07	
Comments: MIRU PETE MARTIN BUCKET RIG. <u>WSMVD</u> SPUD WELL LOCATION ON 09/14/2007 AT 1200 HRS.							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

SHEILA UPCHEGO

Name (Please Print)

Signature

SENIOR LAND SPECIALIST

Title

9/17/2007

Date

RECEIVED

SEP 17 2007

(5/2000)

DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE – Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

KERR-McGEE OIL & GAS ONSHORE LP

3a. Address

1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-7024

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SE/NE SEC. 8, T10S, R23E 2619'FNL, 799'FEL

5. Lease Serial No.

UTU-37355

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

BONANZA 1023-8H

9. API Well No.

4304738222

10. Field and Pool, or Exploratory Area

NATURAL BUTTES

11. County or Parish, State

UINTAH COUNTY, UTAH

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other WELL SPUD
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleation in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

MIRU PETE MARTIN BUCKET RIG. DRILLED 20" CONDUCTOR HOLE TO 40'. RAN 14" 36.7# SCHEDULE 10 PIPE. CMT W/28 SX READY MIX.

SPUD WELL LOCATION ON 09/14/2007 AT 1200 HRS.

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

SHEILA UPCHEGO

Title

SENIOR LAND ADMIN SPECIALIST

Signature

Date

September 17, 2007

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

RECEIVED

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

SEP 25 2007

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

KERR-McGEE OIL & GAS ONSHORE LP

3a. Address

1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-7024

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SE/NE SEC. 8, T10S, R23E 2619'FNL, 799'FEL

5. Lease Serial No.

UTU-37355

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

BONANZA 1023-8H

9. API Well No.

4304738222

10. Field and Pool, or Exploratory Area

NATURAL BUTTES

11. County or Parish, State

UINTAH COUNTY, UTAH

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other SET SURFACE
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	CSG
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

MIRU BILL MARTIN AIR RIG ON 09/16/2007. DRILLED 12 1/4" SURFACE HOLE TO 2130'. RAN 9 5/8" 52 JTS OF 32.3# H-40 AND 2 JTS OF 36# J-55 SURFACE CSG. LEAD CMT W/300 SX PREM CLASS G @15.8 PPG 1.15 YIELD, TAILED CMT W/150 SX PREM CLASS G @15.8 PPG 1.15 YIELD. NO RETURNS TO PIT. TOP OUT W/125 SX PREM CLASS G @15.8 PPG 1.15 YIELD DOWN BACKSIDE. 2ND TOP OUT W/200 SX PREM CLASS G @15.8 PPG 1.15 YIELD. DOWN BACKSIDE GOOD CMT TO SURFACE HOLE STAYED FULL.

WORT.

RECEIVED
SEP 25 2007

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

SHEILA UPCHEGO

Title

SENIOR LAND ADMIN SPECIALIST

Signature

Date

September 19, 2007

DIV. OF OIL, GAS & MINING

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

5. Lease Serial No.

UTU-37355

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

BONANZA 1023-8H

9. API Well No.

4304738222

10. Field and Pool, or Exploratory Area

NATURAL BUTTES

11. County or Parish, State

UINTAH COUNTY, UTAH

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

KERR-McGEE OIL & GAS ONSHORE LP

3a. Address

1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-7024

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SE/NE SEC. 8, T10S, R23E 2619'FNL, 799'FEL

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other FINAL DRILLING
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	OEPRATIONS
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

FINISHED DRILLING FROM 2130' TO 8030' ON 10/28/2007. RAN 4 1/2" 11.6# I-80 PRODUCTION CSG. LEAD CMT W/205 SX PREM LITE II @11.3 PPG 3.02 YIELD. TAILED CMT W/1100 SX 50/50 POZ @14.3 PPG 1.31 YIELD. WASH LINES DROP PLUG & DISPLACE W/124 BBLS CLAYTREAT WATER + 1 GAL MAGNACIDE @8.3 PPG 2320 PSI 555 OVER PSI 1.25 BBLS H2O BLEED OFF 100% RETURNS W/MUD CLEAN. SET MANDREL HANGER W/60K STRING WT TEST MANDREL TO 5000 PSI. NIPPLE DOWN SET NIGHT CAP CLEAN MUD PITS.

RELEASED PIONEER RIG 68 ON 10/29/2007 AT 0000 HRS.

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

SHEILA UPCHEGO

Title

SENIOR LAND ADMIN SPECIALIST

Signature

Date

October 29, 2007

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

RECEIVED

NOV 01 2007

DIV. OF OIL, GAS & MINING

NOTICE

Utah Oil and Gas Conservation General Rule R649-3-21 states that,

- A well is considered completed when the well has been adequately worked to be capable of producing oil or gas or when well testing as required by the division is concluded.
- Within 30 days after the completion or plugging of a well, the following shall be filed:
 - Form 8, Well Completion or Recompletion Report and Log
 - A copy of electric and radioactivity logs, if run
 - A copy of drillstem test reports,
 - A copy of formation water analyses, porosity, permeability or fluid saturation determinations
 - A copy of core analyses, and lithologic logs or sample descriptions if compiled
 - A copy of directional, deviation, and/or measurement-while-drilling survey for each horizontal well

Failure to submit reports in a timely manner will result in the issuance of a Notice of Violation by the Division of Oil, Gas and Mining, and may result in the Division pursuing enforcement action as outlined in Rule R649-10, Administrative Procedures, and Section 40-6-11 of the Utah Code.

As of the mailing of this notice, the division has not received the required reports for

Operator: Kerr-McGee Oil & Gas Onshore, LP

Today's Date: 02/14/2008

Well:	API Number:	Drilling Commenced:
Federal 920-35D drlg rpts/wcr	4304737020	09/08/2007
Bonanza 1023-8H drlg rpts/wcr	4304738222	09/14/2007
Bonanza 1023-4D drlg rpts/wcr	4304737315	09/16/2007
Bonanza 1023-8I drlg rpts/wcr	4304738215	09/22/2007
Bonanza 1023-8O drlg rpts/wcr	4304738305	09/30/2007

IDS 23E 8

To avoid compliance action, required reports should be mailed within 7 business days to:

Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
P.O. Box 145801
Salt Lake City, Utah 84114-5801

If you have questions or concerns regarding this matter, please call (801) 538-5284.

cc: Well File
Compliance File

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

KERR-McGEE OIL & GAS ONSHORE LP

3a. Address

1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-7024

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SE/NE SEC. 8, T10S, R23E 2619'FNL, 799'FEL

5. Lease Serial No.

UTU-37355

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

BONANZA 1023-8H

9. API Well No.

4304738222

10. Field and Pool, or Exploratory Area

NATURAL BUTTES

11. County or Parish, State

UINTAH COUNTY, UTAH

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other PRODUCTION START-UP
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

THE SUBJECT WELL LOCATION WAS PLACED ON PRODUCTION ON 02/07/2008 AT 10:00 AM.

PLEASE REFER TO THE ATTACHED CHRONOLOGICAL WELL HISTORY.

RECEIVED

FEB 25 2008

DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

SHEILA UPCHEGO

Title

SENIOR LAND ADMIN SPECIALIST

Signature

Date

February 12, 2008

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Anadarko Petroleum Corporation
1368 S. 1200 East
Vernal, UT 84078

CHRONOLOGICAL WELL HISTORY

BONANZA 1023-8H

SENE SEC.8, T10S, R23E
UINTAH COUNTY, UT

DATE	ACTIVITY	STATUS
08/30/07	LOCATION STARTED PIONEER 68	
09/14/07	LOCATION COMPLETED PIONEER 68 SET CONDUCTOR	P/L IN, WOBR
09/16/07	SET AIR RIG PIONEER 68	BUILDING
09/20/07	9 5/8" @2089' PIONEER 68	WORT
10/22/07	TD: 2905' Csg. 9 5/8" @ 2089' MW: 9.0 SD: 10/12/07 DSS: 1 Move to Bonanza 1023-8H. RURT. NU and test BOPE. PUDS and drill FE. Rotary spud @ 1900 hrs 10/21/07. Drill from 2130'-2905'. DA @ report time.	
10/23/07	TD: 4866' Csg. 9 5/8" @ 2089' MW: 9.8 SD: 10/12/07 DSS: 2 Drill from 2905'-4866'. DA @ report time.	
10/24/07	TD: 5531' Csg. 9 5/8" @ 2089' MW: 11.1 SD: 10/21/07 DSS: 3 Drill from 4866'-5183'. TFNB. Drill to 5531'. DA @ report time.	
10/25/07	TD: 6671' Csg. 9 5/8" @ 2089' MW: 11.2 SD: 10/21/07 DSS: 4 Drill from 5531'-6671'. DA @ report time.	
10/26/07	TD: 7119' Csg. 9 5/8" @ 2089' MW: 11.3 SD: 10/21/07 DSS: 5 Drill f/ 6671'-6828'. Motor failed. TOOH, LD MM, and c/o bits. TIH and drill conventional to 7119'. DA @ report time.	
10/29/07	TD: 8030' Csg. 9 5/8" @ 2089' MW: 11.8 SD: 10/21/07 DSS: 8 Drill from 7119'-7409'. TFNB. Drill to 8030' TD. Short trip and LDDS. Run Triple Combo. Run and cement 4 1/2" Production Casing. Land casing and release rig @ 0000 hrs 10/29/07.	
01/31/08	MIRU - PU TBG Days On Completion: 1 Remarks: DAY 1 - JSA #1 RDMO BONANZA 1023-9D. ROAD RIG TO BONANZA 1023-8H. MIRU, SPOT EQUIP. NDWH, NUBOP. R/U FLOOR & TBG EQUIP. P/U 3 7/8" MILL & 243 JTS NEW 2 3/8" J55 TBG & RIH. EOT @ 7626'.	
01/31/08	MIRU Days On Completion: 1 Remarks: DAY 1 - JSA #1. RDMO BONANZA 1023-9D. ROAD RIG TO BONANZA 1023-8H. MIRU, SPOT EQUIP. NDWH, NUBOP. R/U FLOOR & TBG EQUIP. P/U 3 7/8" MILL & 243 JTS NEW 2 3/8" J55 TBG & RIH. EOT @ 7626'. 5:30 PM - SWI - SDFN - PREP WELL TO C/O TO PBTD IN AM.	

02/01/08

PU TBG & RIH

Days On Completion: 2

Remarks: DAY 2 – JSA #2. EOT @ 7626'. CONT. PU TBG. & RIH. TAG FILL @ 7973'. PBTD @ 7978'. CIRCK HOLE CLEAN W/115 BBLS RECYCLED WTR. POOH & L/D 14 JTS TBG ON FLOAT. CONT. POOH STDG BACK TBG IN DERRICK. L/D MILL, RD FLOOR & TBG EQUIP. NDBOP & NU FRAC VALVES. MIRU DBL JACK TESTERS. TEST CSG. & FRAC VALVES TO 7500 PSI. (GOOD TEST) RDMO DBL JACK. SWI – SDFN PREP WELL TO FRAC ON MONDAY 02/04/08 W/BJ SERVICES.

02/04/08

PERF

Days On Completion: 5

Remarks: DAY 3 – JSA #3. MIRU CUTTERS & BJ SERVICES. PRESSURE TEST LINES TO 8000 PSI.

STG 1) RIH W/ 3 1/8" GNS, 23 gm, 0.36 HOLES, 90 & 180 DEG. PHASING. PERF THE M.V. @ 7932' – 35', 4 SPF, 7868' – 72', 4 SPF, 7787' – 89', 2 SPF, 7778' – 82', 2 SPF, 40 HOLES. WHP = 31 PSI, BRK 2.7 BPM @ 2820 PSI. ISIP = 2400 PSI, F.G. 0.74. PUMP 100 BBLS @ 50 BPM @ 4300 PSI. 40/40 PERFS OPEN. MP 4319 PSI, MR 51 BPM, AP 4083 PSI, AR 50.6 BPM, ISIP 2450 PSI. F.G. 0.75. NPI 50 PSI, PMPD 1232 BBLS SLK WTR, 36008 LBS TOTAL SAND (5000 LBS TLC) 151 GAL SCALE INHIB.

STG 2) RIH W/ 3 1/8" GNS, 23 gm, 0.36 HOLES, 90 & 120 & 180 DEG. PHASING. SET BAKER 8K CBP @ 7634'. PERF THE M.V. @ 7416' - 18', 2 SPF, 7482' - 85', 2 SPF, 7505' - 07', 3 SPF, 7598' - 7604', 4 SPF, 40 HOLES. WHP = 2147 PSI, BRK 3 BPM @ 2889 PSI. ISIP = 2550 PSI, F.G. 0.78. PUMP 100 BBLS @ 50 BPM @ 4600 PSI. 40/40 PERFS OPEN. MP 7153 PSI, MR 50.3 BPM, AP 5575 PSI, AR 47.3 BPM, ISIP 2670 PSI. F.G. 0.79. NPI 120 PSI, PMPD 2143 BBLS SLK WTR, 79603 LBS TOTAL SAND (5000 LBS TLC) 156 GAL SCALE INHIB.

STG 3) RIH W/ 3 1/8" GNS, 23 gm, 0.36 HOLES, 90 & 120 & 180 DEG. PHASING. SET BAKER 8K CBP @ 7319'. PERF THE M.V. @ 6998' - 7001', 2 SPF, 7142' - 45', 3 SPF, 7279' - 82', 4 SPF, 7285' - 89', 4 SPF, 43 HOLES. WHP = 1408 PSI, BRK 3 BPM @ 2307 PSI. ISIP = 1900 PSI, F.G. 0.70. PUMP 100 BBLS @ 51.3 BPM @ 4400 PSI. 33/43 PERFS OPEN. MP 4510 PSI, MR 52.1 BPM, AP 4005 PSI, AR 51.3 BPM, ISIP 2050 PSI. F.G. 0.72. NPI 150 PSI, PMPD 1486 BBLS SLK WTR, 54047 LBS TOTAL SAND (5000 LBS TLC) 119 GAL SCALE INHIB.

STG 4) RIH W/ 3 1/8" GNS, 23 gm, 0.36 HOLES, 90 DEG. PHASING. SET BAKER 8K CBP @ 6948'. PERF THE M.V. @ 6530' - 33', 4 SPF, 6760' - 64', 4 SPF, 6771' - 75', 4 SPF, 44 HOLES. WHP = 200 PSI, BRK 5 BPM @ 2519 PSI. ISIP = 1700 PSI, F.G. 0.69. PUMP 80 BBLS @ 49.8 BPM @ 3940 PSI. 34/44 PERFS OPEN. MP 3963 PSI, MR 51 BPM, AP 3703 PSI, AR 50.3 BPM, ISIP 2380 PSI. F.G. 0.80. NPI 480 PSI, PMPD 757 BBLS SLK WTR, 28847 LBS TOTAL SAND (5000 LBS TLC) 26 GAL SCALE INHIB.

KILL PLUG) RIH SET 8K BAKER CBP @ 6490'. POOH & LD WIRELINE TOOLS. RDMO CUTTERS & BJ SERVICES. TOTAL 30/50 SAND = 198,505 LBS (INCL. 20,260 LBS TLC). TOTAL FLUID 5,618 BBLS. RD FLOOR. ND FRAC VALVES, NUBOP. RU FLOOR & TBG EQUIP. CHANGE OUT RIG PIPE TONGS. 5:00 PM - SWI – SDFN PREP WELL TO RUN TBG & DRLG PLUGS IN AM. 02/05/08

02/05/08

DRL CBP'S

Days On Completion: 6

Remarks: DAY 4 – JSA #4. PU 3 7/8" BIT, POBS W/SN & RIH ON NEW 2 3/8" J55 TBG. TAG SND @ 6465'. RU SWVL & PMP. EST. CIRC. W/RECYCLED WTR. PT BOP's TO 3000 PSI. C/O 25' SAND. PLUG @ 6490' PLUG 1 @ 6490') DRLG BAKER 8K CBP IN 4 MIN. 50 PSI DIFF. RIH TAG SND @ 6780'. C/O 25' SND. FCP = 25 PSI PLUG 2 @ 6805') DRLG BAKER

8K CBP IN 4 MIN. 100 PSI DIFF. RIH TAG SND @ 7299'. C/O 20' SND. FCP = 25 PSI PLUG 3 @ 7319') DRLG BAKER 8K CBP IN 5 MIN. 150 PSI DIFF. RIH TAG SND @ 7604', C/O 30' SND. FCP = 200 PSI PLUG 4 @ 7634') DRLG BAKER 8K CBP IN 5 MIN. 50 PSI DIFF. RIH TAG SND @ 7953'. C/O 25' SND. TAG PBD @ 7978'. CIRC WELL CLEAN. FCP 200 PSI. RD SWVL. POOH & LD 30 JTS TBG ON TRL. (TOTAL OF 55 JTS ON TRL). LAND TBG ON HANGER WITH 225 JTS. EOT @ 7076.58' & POBS W/SN @ 7074.38'. AVG 4.5 MIN/PLUG & 100' SND. RD FLOOR & TBG EQUIP. NDBOP, DROP BALL DN TBG, NUWH. PMP OFF THE BIT @ 2100 PSI. WAIT 30 MIN FOR BALL TO FALL TO BTM. OPEN WELL TO F.B.T. ON 20/64 CHOKE. FTP 1050 PSI. SICP 1700 PSI. 4:30 PM) TURN WELL OVER TO F.B.C. RECOVERED 530 BBLS. 5087 BBLS TO RECOVER. RDMO. ROAD RIG TO BONANZA 1023-8I. SDFN.

02/07/08	FLOWBACK REPORT: CP 1375#, TP 1750#, CK 20/64", 42 BWPH, LOAD REC'D 1197 BBLS, REMAINING LTR 2908 BBLS WENT ON SALES: @ 10:00 AM, 1800 MCF, 1950 TBG, 3175 CSG, 20/64 CK, 42 BBWH FLOWBACK REPORT: CP 3325#, TP 1700#, CK 20/64", 27 BWPH, LOAD REC'D 840 BBLS, REMAINING LTR 2068 BBLS
02/08/08	ON SALES: 1080 MCF, 5 BC, 684 BW, TP: 1700#, CP: 3325#, 20/64 CHK, 24 HRS, LP: 147#. FLOWBACK REPORT: CP 2775#, TP 1775#, CK 20/64", 12 BWPH, LOAD REC'D 481 BBLS, REMAINING LTR 1587 BBLS
02/09/08	ON SALES: 1910 MCF, 5 BC, 648 BW, TP: 1025#, CP: 2975#, 20/64 CHK, 24 HRS, LP: 138#.
02/10/08	ON SALES: 1982 MCF, 5 BC, 288 BW, TP: 1656#, CP: 2077#, 20/64 CHK, 24 HRS, LP: 132#.
02/11/08	ON SALES: 2106 MCF, 5 BC, 270 BW, TP: 1619#, CP: 1938#, 20/64 CHK, 24 HRS, LP: 128#.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

FORM APPROVED
OMB NO. 1004-0137
Expires: November 30, 2000

5. Lease Serial No.
UTU-37355

1a. Type of Well ☐ Oil Well ☒ Gas ☐ Dry Other
b. Type of Completion: ☒ New ☐ Work Over ☐ Deepen ☐ Plug Back ☐ Diff. Resvr.
Other _____

6. If Indian, Allottee or Tribe Name

7. Unit or CA Agreement Name and No.

2. Name of Operator

KERR-MCGEE OIL & GAS ONSHORE LP

8. Lease Name and Well No.

BONANZA 1023-8H

3. Address

1368 SOUTH 1200 EAST, VERNAL, UTAH 84078

3a. Phone No. (include area code)

(435) 781-7024

9. API Well No.

4304738222

4. Location of Well (Report locations clearly and in accordance with Federal requirements) *

At surface

SE/NE 2619'FNL, 799'FEL

10. Field and Pool, or Exploratory

NATURAL BUTTES

At top prod. interval reported below

11. Sec., T., R., M., or Block and
Survey or Area SEC. 8, T10S, R23E

12. County or Parish

UINTAH

13. State

UTAH

At total depth

14. Date Spudded

09/14/07

15. Date T.D. Reached

10/28/07

16. Date Completed

☐ D & A ☒ Ready to Prod.

02/07/08

17. Elevations (DF, RKB, RT, GL)*

5285'GL

18. Total Depth: MD
TVD

8030'

19. Plug Back T.D.: MD
TVD

7978'

20. Depth Bridge Plug Set: MD
TVD

21. Type Electric & Other Mechanical Logs Run (Submit copy of each)

22. Was well cored? ☒ No ☐ Yes (Submit copy)

Was DST run? ☒ No ☐ Yes (Submit copy)

Directional Survey? ☒ No ☐ Yes (Submit copy)

CBL-CCL-GR, SD/DSN/ARRAY COMP TRUE RES

23. Casing and Liner Record (Report all strings set in well)

Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sk. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
20"	14"	36.7#		40'		28 SX			
12 1/4"	9 5/8"	32.3# 36#		2130'		775 SX			
7 7/8"	4 1/2"	11.6#		8030'		1305 SX			

24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Set (MD)
2 3/8"	7076'							

25. Producing Intervals

26. Perforation Record

Formation	Top	Bottom	Perforated Interval	Size	No. Holes	Perf. Status
A) MESAVERDE	6530'	7935'	6530'-7935'	0.36	167	OPEN
B)						
C)						
D)						

27. Acid, Fracture, Treatment, Cement Squeeze, Etc.

Depth Interval	Amount and type of Material
6530'-7935'	PMP 5618 BBLS SLICK H2O & 198,505# 30/50 OTTOWA SD

RECEIVED

MAR 03 2008

DIV. OF OIL, GAS & MINING

28. Production - Interval A

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
02/07/08	02/11/08	24	→	5	2,106	270			FLOWS FROM WELL
Choke Size	Tbg. Press. Flwg. 1619#	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Well Status	
20/64	SI	1938#	→	5	2106	270			PRODUCING GAS WELL

28a. Production - Interval B

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press.	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Well Status	
			→						

(See instructions and spaces for additional data on reverse side)

28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas : Oil Ratio	Well Status	

28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas : Oil Ratio	Well Status	

29. Disposition of Gas (Sold, used for fuel, vented, etc.)

SOLD

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top
					Meas. Depth
WASATCH MESAVERDE	4024' 6061'	6061'			

32. Additional remarks (include plugging procedure):

33. Circle enclosed attachments:

- | | | | |
|---|--------------------|---------------|-----------------------|
| 1. Electrical/Mechanical Logs (1 full set req'd.) | 2. Geologic Report | 3. DST Report | 4. Directional Survey |
| 5. Sundry Notice for plugging and cement verification | 5. Core Analysis | 7. Other: | |

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions)*

Name (please print) SHEILA UPCHEGOTitle SENIOR LAND ADMIN SPECIALISTSignature Date 02/25/08

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-37355			
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME:			
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: BONANZA 1023-8H			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2619 FNL 0799 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 08 Township: 10.0S Range: 23.0E Meridian: S		9. API NUMBER: 43047382220000			
PHONE NUMBER: 720 929-6515 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES			
COUNTY: UTAH		STATE: UTAH			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION	TYPE OF ACTION				
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 4/28/2011 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input checked="" type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/> </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input checked="" type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input checked="" type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. The operator requests authorization to temporarily abandon the subject well location. The operator proposes to temporarily abandon the well to drill the Bonanza 1023-8H Pad, which consists of the following wells: Bonanza 1023-8G4DS, Bonanza 1023-8H2DS, Bonanza 1023-8H3DS and Bonanza 1023-8H4DS. Please see attached procedures.					
Accepted by the Utah Division of Oil, Gas and Mining		Date: 04/28/2011 By:			
NAME (PLEASE PRINT) Gina Becker		PHONE NUMBER 720 929-6086			
SIGNATURE N/A		TITLE Regulatory Analyst II			
DATE 4/28/2011					

BONANZA 1023-8H
2619' FNL & 799' FEL
SENE SEC.8, T10S, R23E
Uintah County, UT

KBE: 5303'
GLE: 5285'
TD: 8030' (10/28/07)
PBTD: 7978'

API NUMBER: 4304738222
LEASE NUMBER: UTU-37355
WINS#: 95581
WI: 100.0000%
NRI: 77.50000%

CASING: 12.25" hole
9.625" 32.3# & 36# H-40 @ 2130'
Cemented with 775 sx

7.875" hole
4.5" 11.6# I-80 @ 8030'
Cemented with 1305 sx, TOC @ 280' per CBL

TUBING: 2 3/8" 4.7# J-55 tubing landed at 7328'

PERFORATIONS: Mesaverde 6530' – 7935'

Tubular/Borehole	Drift inches	Collapse psi	Burst Psi	Capacities		
				Gal./ft.	Cuft/ft.	Bbl./ft.
2.375" 4.7# J-55 tbg.	1.901	8100	7700	0.1626	0.02171	0.00387
4.5" 11.6# N/M/I-80 csg	3.875	6350	7780	0.6528	0.0872	0.0155
9.625" 32.3# H-40 csg	8.845	1400	2270	3.3055	0.4418	0.0787
Annular Capacities						
2.375" tbg. X 4.5" 11.6# csg.				0.4226	0.0565	0.01
4.5" csg. X 9.625" 32.3# csg.				2.478	0.3314	0.059
4.5" csg. X 7.875" hole				1.7052	0.2278	0.0406
9.625" csg. X 12.25" hole				2.3436	0.3132	0.0558

GEOLOGIC INFORMATION:

Formation	Depth to top, ft.	Tech. Pub. #92 Base of USDW's
Uinta	Surface	USDW Elevation ~1500' MSL
Wasatch	4024'	USDW Depth ~3803' KBE
Mesaverde	6061'	

Recommended future action for disposition of well bore:

Temporarily abandon the wellbore during the drilling and completion operations of the Bonanza 1023-8H pad wells. Return to production as soon as possible once completions are done.

BONANZA 1023-8H TEMPORARY ABANDONMENT PROCEDURE - Workorder# 88129081

GENERAL

- H₂S MAY BE PRESENT. CHECK FOR H₂S AND TAKE APPROPRIATE PRECAUTIONS.
- CEMENT QUANTITIES BELOW ASSUME NEAT CLASS G, YIELD 1.145 CUFT./SX. IF A DIFFERENT PRODUCT IS USED, WELLSITE PERSONNEL ARE RESPONSIBLE FOR CORRECTING QUANTITIES TO YIELD THE STATED SLURRY VOLUME. WHEN SQUEEZING, INCLUDE 10% EXCESS PER 1000' OF DEPTH.
- TREATED FRESH WATER WILL BE PLACED BETWEEN ALL PLUGS INSTEAD OF BRINE.
- ALL DISPLACEMENT FLUID SHALL CONTAIN CORROSION INHIBITOR AND BIOCIDES. PREMIX 5 GALLONS PER 100 BBLs FLUID.
- NOTIFY BLM 24 HOURS BEFORE MOVING ON LOCATION.

PROCEDURE

Note: An estimated 24 sx Class "G" cement needed for procedure

Note: No gyro on file

1. MIRU. KILL WELL AS NEEDED. ND WH, NU AND TEST BOPE.
2. RU WIRELINE AND MAKE A GAUGE RING RUN TO CHECK FOR FILL AND PREP FOR GYRO SURVEY. **A GPS READING WILL NEED TO BE TAKEN AT THE WELL SITE AND RECORDED IN OPENWELLS. PLEASE TAKE IT TO THE 6TH DECIMAL PLACE.**
3. Run Gyro survey.
4. **PLUG #1, ISOLATE MV PERFORATIONS (6530'–7935'):** RIH W/ 4 ½" CBP. SET @ ~6480'. RELEASE CBP, PUH 10', BRK CIRC W/ FRESH WATER. PRESSURE TEST CASING TO 500 PSI. INFORM ENGINEERING IF IT DOESN'T TEST. DISPLACE A MINIMUM OF **8 SX/ 1.6 BBL/ 8.72 CUFT.** ON TOP OF PLUG. PUH ABOVE TOC (~6380'). REVERSE CIRCULATE W/ TREATED FRESH WATER.
5. **PLUG #2, PROTECT WASATCH TOP (4024'):** PUH TO ~4125'. BRK CIRC W/ FRESH WATER. DISPLACE A MINIMUM OF **16 SX/ 3.2 BBL/ 17.88 CUFT** AND BALANCE PLUG W/ TOC @ ~3920' (205' COVERAGE). PUH ABOVE TOC. REVERSE CIRCULATE W/ TREATED FRESH WATER.
6. LOWER WELLHEAD TO GROUND LEVEL TO ACCOMMODATE DRILLING OPS AND INSTALL MARKER PER BLM GUIDELINES.
7. RDMO. TURN OVER TO DRILLING OPERATIONS.

ALM 4/19/11

RECEIVED Apr. 28, 2011

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-37355			
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME:			
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: BONANZA 1023-8H			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2619 FNL 0799 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 08 Township: 10.0S Range: 23.0E Meridian: S		9. API NUMBER: 43047382220000			
PHONE NUMBER: 720 929-6515 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES			
COUNTY: UINTAH		STATE: UTAH			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION	TYPE OF ACTION				
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 5/3/2011 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input checked="" type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: Subsurface Commingle </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input checked="" type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: Subsurface Commingle
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input checked="" type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: Subsurface Commingle			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. The operator requests authorization to re-complete the subject well location. The operator proposed to re-complete the Wasatch formation. The operator also requests authorization to commingle the newly Wasatch and existing Mesaverde formations. Please refer to the attached re-completion procedures.					
Accepted by the Utah Division of Oil, Gas and Mining Date: 05/09/2011 By:					
NAME (PLEASE PRINT) Gina Becker		PHONE NUMBER 720 929-6086			
SIGNATURE N/A		TITLE Regulatory Analyst II DATE 5/3/2011			



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Sundry Conditions of Approval Well Number 43047382220000

Authorization: Board Cause No. 179-14 .

Greater Natural Buttes Unit



BONANZA 1023-8H RE-COMPLETIONS PROCEDURE

DATE:2/1/2011
AFE#:
USER ID:JVN975 (Frac Invoices Only)

COMPLETIONS ENGINEER: Michael Sollee, Denver, CO
(720)-929-6057 (Office)
(832)-859-0515 (Cell)

SIGNATURE:

ENGINEERING MANAGER: JEFF DUFRESNE

SIGNATURE:

REMEMBER SAFETY FIRST!

Name: Bonanza 1023-8H
Location: SE NE Sec 8 T10S R23E
Uintah County, UT
Date: 2/1/2011

ELEVATIONS: 5285' GL 5303' KB

TOTAL DEPTH: 8030' **PBTD:** 7978'
SURFACE CASING: 9 5/8", 32.3# H-40 & 36# J-55 ST&C @ 2089'
PRODUCTION CASING: 4 1/2", 11.6#, I-80 LT&C @ 8022'
 Marker Joint **4050-4071'**

TUBULAR PROPERTIES:

	BURST (psi)	COLLAPSE (psi)	DRIFT DIA. (in.)	CAPACITIES	
				(bbl/ft)	(gal/ft)
2 3/8" 4.7# J-55 tbg	7,700	8,100	1.901"	0.00387	0.1624
4 1/2" 11.6# I-80 (See above)	7780	6350	3.875"	0.0155	0.6528
2 3/8" by 4 1/2" Annulus				0.0101	0.4227

TOPS:

1105' Green River Top*
 1314' Bird's Nest Top*
 1688' Mahogany Top*
 4024' Wasatch Top
 6060' Mesaverde Top

*Estimated

BOTTOMS:

6060' Wasatch Bottom
 8030' Mesaverde Bottom (TD)

T.O.C. @ 1600'

GENERAL:

- A minimum of **8** tanks (cleaned lined 500 bbl) of recycled water will be required. Note: Use biocide in tanks and the water needs to be at least 45°F at pump time.
- All perforation depths are from Halliburtons Induction-Density-Neutron log dated 10/28/2007
- **3** fracturing stages required for coverage.
- Procedure calls for **4** CBP's (**8000** psi) .
- Calculate open perforations after each breakdown. If less than 60% of the perforations appear to be open, ball out with 15% HCl.
- Pump scale inhibitor at 3 gpt (in pad and until 1.25 ppg ramp up is reached) and 10 gpt in all flushes except the final stage. Remember to pre-load the casing with scale inhibitor for the very first stage with 10 gpt.
- 30/50 mesh Ottawa sand, **Slickwater frac.**
- Maximum surface pressure **6200** psi.

- Flush volumes are the sum of slick water and acid used during displacement (include scale inhibitor as mentioned above). Stage acid and scale inhibitor if necessary to cover the next perforated interval.
- **Call flush at 0 PPG @ inline densimeters. Slow to 5 bbl/min over last 10-20 bbls of flush. Flush to top perf.**
- **If distance between plug and top perf of previous stage is less than 50', it is considered to be tight spacing - over flush stage by 5 bbls (from top perf)**
- Pump 20/40 mesh curable resin coated sand last 5,000# of all frac stages
- Tubing Currently Landed @~7328
- Originally completed on 2/4/2008

Existing Perforations:

Stage	Zones	Perforations		SPF	Holes
		Top, ft	Bottom, ft		
1	MESAVERDE	7778	7782	2	8
	MESAVERDE	7787	7789	2	4
	MESAVERDE	7868	7872	4	16
	MESAVERDE	7932	7935	4	12
	# of Perfs/stage				40
2	MESAVERDE	7416	7418	2	4
	MESAVERDE	7482	7485	2	6
	MESAVERDE	7505	7507	3	6
	MESAVERDE	7598	7604	4	24
	# of Perfs/stage				40
3	MESAVERDE	6998	7001	2	6
	MESAVERDE	7142	7145	3	9
	MESAVERDE	7279	7282	4	12
	MESAVERDE	7285	7289	4	16
	# of Perfs/stage				43
4	MESAVERDE	6530	6533	4	12
	MESAVERDE	6760	6764	4	16
	MESAVERDE	6771	6775	4	16
	# of Perfs/stage				44

Relevant History

- FEB 2008: Completed with 4 SW frac stages in the Mesaverde. Cleaned out to 7978'. Landed tubing high at 7077', pumped off POBS.
- JUN 2008: Workover. LD 40jts 2 3/8" tbg. C/O to 7970'. Landed tubing @ 7322'.
- SEP 2008 Workover. LD 28 jts 2 3/8" tbg. C/O to 7970'. Land tubing @ 7328'.
- JUN 2010: Slickline. Stacked out at 7215. Ran sample bailer to 7265. Looked like mud in bailer.

H2S History:

BONANZA 1023-8H

Date	H2S H2S_SEPARATO R_PPM
10/1/2008	5.00
11/1/2008	0.00
12/1/2008	8.00
1/1/2009	3.00
2/1/2009	0.00
3/1/2009	8.00
4/1/2009	4.00
5/1/2009	5.00
6/1/2009	0.00
7/1/2009	0.00
8/1/2009	
9/1/2009	0.00
10/1/2009	5.00
11/1/2009	0.00

PROCEDURE: (If using any chemicals for pickling tubing or H2S Scavenging, have MSDS for all chemicals prior to starting work.)

1. MIRU. Control well with recycled water and biocide as required. ND WH, NU BOP's and test.
2. If the tubing is below the proposed CBP depth, TOO H with 2-3/8", 4.7#, J-55 (or N-80) tubing (currently landed at ~7328'). Visually inspect for scale and consider replacing if needed. If the tubing is above the proposed CBP depth, RIH with tubing and tag for fill before TOO H.
3. If tbg looks ok consider running a gauge ring to 6026 (50' below proposed CBP). Otherwise P/U a mill and C/O to 6026 (50' below proposed CBP).
4. Set 8000 psi CBP at ~ 5976'. ND BOPs and NU frac valves. Test frac valves and casing to 1000 and 3500 psi for 15 minutes each and to 6200 psi for 30 minutes. As per standard operating procedure install steel blowdown line to reserve pit from 4-1/2" X 8-5/8" annulus with pressure relief valve in line. Pressure relief will be set to release at 500 psig. Lock **OPEN** the Braden head valve. Annulus will be monitored throughout stimulation. If release occurs, stimulation will be shut down. Well conditions will be assessed and actions taken as necessary to secure the well. UDOGM will be notified if a release to the annulus occurs.
5. Perf the following with 3-3/8" gun, 23 gm, 0.36"hole:

Zone	From	To	spf	# of shots
WASATCH	5894	5897	4	12
WASATCH	5943	5946	4	12
6. Breakdown perfs and establish injection rate (include scale inhibitor in fluid). Spot 250 gals of 15% HCL and let soak 5-10 min. Fracture as outlined in Stage 1 on attached listing. Under-displace to ~5894' and trickle 250gal 15%HCL w/ scale inhibitor in flush .
7. Set 8000 psi CBP at ~5,690'. Perf the following 3-3/8" gun, 23 gm, 0.36"hole:

Zone	From	To	spf	# of shots
WASATCH	5571	5573	4	8
WASATCH	5656	5660	4	16

8. Breakdown perfs and establish injection rate. Fracture as outlined in Stage 2 on attached listing. Under-displace to ~5571' and trickle 250gal 15%HCL w/ scale inhibitor in flush.
9. Set 8000 psi CBP at ~5,480'. Perf the following with 3-3/8" gun, 23 gm, 0.36" hole:

Zone	From	To	spf	# of shots
WASATCH	5258	5259	3	3
WASATCH	5292	5294	3	6
WASATCH	5373	5374	3	3
WASATCH	5421	5422	3	3
WASATCH	5448	5450	3	6
10. Breakdown perfs and establish injection rate. Fracture as outlined in Stage 3 on attached listing. Under-displace to ~5258' flush only with recycled water.
11. Set 8000 psi CBP at ~5,208'.
12. ND Frac Valves, NU and Test BOPs.
13. TIH with 3 7/8" bit, pump off sub, SN and tubing.
14. Drill plugs and clean out to PBTD. Shear off bit and land tubing at $\pm 7386'$ unless indicated otherwise by the well's behavior. The well will be commingled at this time.
15. Clean out well with foam and/or swabbing unit until steady flow has been established from completion.
16. RDMO. Leave casing valve open.

For design questions, please call
Michael Sollee, Denver, CO
(720)-929-6057 (Office)
(832)-859-0515 (Cell)

For field implementation questions, please call
Jeff Samuels, Vernal, UT
435-781 7046 (Office)

NOTES:

If using any chemicals for pickling tubing or H2S Scavenging, have MSDS for all chemicals prior to starting work

Acid Pickling and H2S Procedures (If Required)

****PROCEDURE FOR PUMPING ACID DOWN TBG**

WHEN FINDING SCALE IN TUBING THAT IS ACID SOLUBLE, ENSURE THAT PLUNGER EQUIPMENT IS REMOVED AND ABLE TO PUMP DOWN TBG. INSTALL A 'T' IN PUMP LINE W/2" VALVE THAT NALCO CAN TIE INTO. HAVE 60 BBLS 2% KCL MIXED W/ 10-15 GAL H2S SCAVENGER IN RIG FLAT TANK. (WE USED THE RIG FLAT TANK FOR MIXING CHEMICAL SO WE DIDN'T HAVE THE CHEMICAL IN ALL FLUIDS ON LOCATION, ONLY WHAT WE NEEDED TO PUMP DOWN HOLE)

1. PUMP 5-10 BBLS 2% KCL DOWN TBG (NALCO CANNOT PUMP AGAINST PRESSURE)
2. NALCO WILL PUMP 3 DRUMS HCL (31%) INTO PUMP LINE.
3. FLUSH BEHIND ACID WITH 10-15 BBL 2% KCL
4. PUMP 2—30 BBL 2% W/ H2S SCAVENGER DOWN TBG.
5. PUMP REMAINDER OF 2% W/ H2S SCAVENGER DOWN CASING AND SHUT WELL IN FOR MINIMUM OF 2 HRS.
6. OVER DISPLACE DOWN TBG AND CSG TO FLUSH ACID AND SCAVENGER INTO FORMATION
7. MONITOR TUBING FOR FLOW AND CASING FOR H2S NOW AS POOH W/ TUBING.

**** PROCEDURE FOR PUMPING H2S SCAVENGER WITHOUT ACID**

PRIOR TO RIG MOVING ON OR AS RIG PULLS ONTO LOCATION. TEST CASING, TUBING AND SEPARATOR FOR H2S. IF FOUND MAKE SURE THAT PLUNGER SYSTEM IS REMOVED (IT IS POSSIBLE TO PUMP AROUND PLUNGERS BUT SOME WILL HAVE A STANDING VALVE IN SEATING NIPPLE).

1. MIX 10-15 GAL H2S SCAVENGER WITH 60-100 BBL 2% KCL IN RIG FLAT TANK.
2. PUMP 25 BBLS MIXTURE DOWN TUBING AND REST DOWN CASING. SHUT WELL IN FOR 2 HOURS.
3. IF WELL HAS PRESSURE AFTER 2 HOURS – RETEST CASING AND TUBING FOR H2S.
4. FLUSH TUBING AND CASING PUSHING H2S SCAVENGER INTO FORMATION.
5. MONITOR TUBING FOR FLOW AND CASING FOR H2S NOW AS POOH W/ TUBING.

** As per APC standard operating procedure, APC foreman will verify ALL volumes pumped and record on APC Volume Report Form

Key Contact information

Completion Engineer

Michael Sollee: 832-859-0515, 720-929-6057

Production Engineer

Kyle Bohannon: 804-512-1985, 435-781-7068

Completion Supervisor Foreman

Jeff Samuels: 435-828-6515, 435-781-7046

Completion Manager

Jeff Dufresne: 720-929-6281, 303-241-8428

Vernal Main Office

435-789-3342

Emergency Contact Information—Call 911

Vernal Regional Hospital Emergency: 435-789-3342

Police: (435) 789-5835

Fire: 435-789-4222

Total Stages	3	stages
Last Stage Flush	3432	gals

Friction Reducer	63	gals @	0.5	GPT
Surfactant	127	gals @	1.0	GPT
Clay Stabilizer	127	gals @	1.0	GPT
15% Hcl	750	gals @	250	gal/stg
Iron Control for acid	4	gals @	5.0	GPT of acid
Surfactant for acid	1	gals @	1.0	GPT of acid
Corrosion Inhibitor for acid	2	gals @	2.0	GPT of acid

Third Party Supplied Chemicals Job Totals - Include Pumping Charge if Applicable

Scale Inhibitor	361	gals pumped per schedule above
Biocide	63	gals @ 0.5 GPT

Fracturing Schedules

Name Bonanza 1023-8H

Slickwater Frac

Copy to new book

Recomplete?	Y
Pad?	N
ACTS?	N

Swabbing Days	0	Enter Number of swabbing days here for recompletes
Production Log	0	Enter 1 if running a Production Log
DFIT	0	Enter Number of DFITs

Stage	Zone	Perfs		Holes	Rate BPM	Fluid Type	Initial ppg	Final ppg	Fluid	Volume gals	Cum Vol gals	Volume BBLs	Cum Vol BBLs	Fluid % of frac	Sand % of frac	Sand lbs	Cum. Sand lbs	Footage from CBP to Flush	Scale Inhib., gal.
1	WASATCH	5894	5897	4	12	Varied	0.25	1	Pump-in test			0	0						
	WASATCH	5943	5946	4		0 ISIP and 5 min ISIP			0 ISIP and 5 min ISIP	6,273	6,273	149	149	25.0%	0.0%	0	0		37
	WASATCH					50 Slickwater Pad			Slickwater	12,546	18,819	299	448	50.0%	45.5%	7,841	7,841	0	19
	WASATCH					50 Slickwater Ramp			Slickwater	6,273	25,092	149	597	25.0%	54.5%	9,410	17,251	0	38
	WASATCH					50 Flush (4-1/2)			Slickwater	3,848	28,940	92	689				17,251	0	0
	WASATCH				12	ISDP and 5 min ISDP		2	Slickwater										0
	WASATCH								Slickwater		28,940	92	689				17,251		0
	WASATCH																	0	0
	WASATCH																	0	0
	WASATCH																	0	0
	WASATCH																		37
	WASATCH				24	Look			Sand laden Volume		25,092	Flush depth	5894	gal/md-ft	180,000	123,750	lbs sand/md-ft	204	130
	WASATCH																		
	WASATCH																		
	WASATCH																		
	WASATCH																		
2	WASATCH	5571	5573	4	8	Varied	0.25	1	Pump-in test			0	0						
	WASATCH	5656	5660	4		0 ISIP and 5 min ISIP			0 ISIP and 5 min ISIP	9,198	9,198	219	219	25.0%	0.0%	0	0		28
	WASATCH					50 Slickwater Pad			Slickwater	18,396	27,594	438	657	50.0%	45.5%	11,498	11,498	0	55
	WASATCH					50 Slickwater Ramp			Slickwater	9,198	36,792	219	876	25.0%	54.5%	13,797	25,295	0	0
	WASATCH					50 Flush (4-1/2)			Slickwater	3,637	40,429	87	963				25,295	0	0
	WASATCH				24	Look			Slickwater		40,429	87	963				25,295		0
	WASATCH																	0	0
	WASATCH																	0	0
	WASATCH																	0	0
	WASATCH																	0	0
	WASATCH				24	Look			Sand laden Volume		36,792	Flush depth	5571	gal/md-ft	180,000	123,750	lbs sand/md-ft	91	118
	WASATCH																		
	WASATCH																		
	WASATCH																		
	WASATCH																		
3	WASATCH	5258	5259	3	3	Varied	0.25	1.5	Pump-in test			0	0						
	WASATCH	5292	5294	3		0 ISIP and 5 min ISIP			0 ISIP and 5 min ISIP	8,609	8,609	205	205	15.0%	0.0%	0	0		26
	WASATCH	5373	5374	3		50 Slickwater Pad			Slickwater	28,698	37,307	683	888	50.0%	35.7%	25,110	25,110	0	86
	WASATCH	5421	5422	3		50 Slickwater Ramp			Slickwater	20,088	57,395	478	1,367	35.0%	64.3%	45,199	70,309	0	0
	WASATCH	5448	5450	3		50 Flush (4-1/2)			Slickwater	3,432	60,827	82	1,448				70,309	0	0
	WASATCH				21	Look			Slickwater		60,827	82	1,448				70,309		0
	WASATCH																	0	0
	WASATCH																	0	0
	WASATCH																	0	0
	WASATCH																	0	0
	WASATCH				69	29.0	<< Above pump time (min)		Sand laden Volume		57,395	Flush depth	5258	gal/md-ft	50,000	61,250	lbs sand/md-ft	50	112
	WASATCH																		
	WASATCH																		
	WASATCH																		
	WASATCH																		
Totals										Total Fluid	130,196 gals	3,100 bbls	3,100 bbls			Total Sand	112,854		
													6.9 tanks				Total Scale Inhib. =		361

Name Bonanza 1023-8H
Perforation and CBP Summary

Stage	Zones	Perforations		SPF	Holes		Fracture Coverage		
		Top, ft	Bottom, ft						
1	WASATCH	5894	5897	4	12		5889	to	5901
	WASATCH	5943	5946	4	12		5938.5	to	5947
	WASATCH								
					Look				
	# of Perfs/stage				24		CBP DEPTH	5,690	
2	WASATCH	5571	5573	4	8		5565.5	to	5576
	WASATCH	5656	5660	4	16		5646	to	5661
	WASATCH								
					Look				
	# of Perfs/stage				24		CBP DEPTH	5,480	
3	WASATCH	5258	5259	3	3		5254.5	to	5261
	WASATCH	5292	5294	3	6		5288	to	5301
	WASATCH	5373	5374	3	3		5371	to	5376
	WASATCH	5421	5422	3	3		5419.5	to	5428
	WASATCH	5448	5450	3	6		5440.5	to	5452
	WASATCH								
					Look				
	# of Perfs/stage				21		CBP DEPTH	5,208	
	Totals				69				

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-37355
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: BONANZA 1023-8H
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2619 FNL 0799 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 08 Township: 10.0S Range: 23.0E Meridian: S		9. API NUMBER: 43047382220000
PHONE NUMBER: 720 929-6515 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 7/19/2011	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input checked="" type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION	
<input type="checkbox"/> DRILLING REPORT Report Date:	OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. The operator has concluded the temporary abandonment operations on the subject well location on 07/19/2011. This well has been temporarily abandoned in order to drill the BONANZA 1023-8H pad wells. Please see the attached chronological well history for details. Thank you.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY		
NAME (PLEASE PRINT) Gina Becker		PHONE NUMBER 720 929-6086
SIGNATURE N/A		TITLE Regulatory Analyst II
DATE 7/28/2011		

RECEIVED Jul. 28, 2011

US ROCKIES REGION

Operation Summary Report

Well: BONANZA 1023-8H						Spud Date: 10/21/2007			
Project: UTAH-UINTAH			Site: BONANZA 1023-8H PAD				Rig Name No: MILES 2/2		
Event: ABANDONMENT			Start Date: 7/13/2011				End Date: 7/19/2011		
Active Datum: RKB @5,302.99ft (above Mean Sea Leve			UWI: BONANZA 1023-8H						
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation	
7/18/2011	7:00 - 7:30	0.50	ABAND	48		P		MIRU	
	7:30 - 18:00	10.50	ABAND	45		P		MIRU 1300# CSG-TBG, KILL WELL, 20 BBLS, TBG, 30 BBLS CSG, NDWH, NU BOP'S, TEST BOP'S, UNLAND TBG, RU PRS, SCAN TBG, STD BACK 102 STDS, LAY DWN BALANCE, RD PRS. RU JW WIRE LINE, PU GAUGE RING, RUN TO 6470', POOH, PU 10 K CBP, TIH SET CBP AT 6460', POOH, RD JW WIRE LINE, TIH 00 STDS, SWIFN PULLED TBG 231 JTS J-55, 180 JTS YB, 51JTS RED BAND	
7/19/2011	7:00 - 7:30	0.50	ABAND	48		P		CEMENTING	
	7:30 - 7:30	0.00	ABAND	51		P		RU PRO PETRO, BREAK CIRC, TEST CSG TO 500# 5 MIN, ALL CEMENT USED, CLASS G, YIELD 1.145, DENISTY 15.8#, 4.9 GW/SX, SET PLUG #1 ON TOP OF CBP, 6460', PUMP 2.6 BBLS FRESH WTR, 10 SX, 2 BBLS CEMENT, DISPLACE WITH 1 BBL FRESH 23.5 BBLS T-MAC, POOH LAY DWN 73 JTS ON TLR, TO 4125', PUMP 2.6 BBLS FRESH, 20 SX, 4.1 BBLS CEMENT, DISPLACE WITH 1 BBL FRESH, 13.5 BBLS T-MAC, RD PRO PETRO, POOH LAY DWN BALANCE OF TBG ON TLR, ND BOP'S, CALL FMC TO PULL WH, RDMO CALLED CDC JIM 9:45 AM. N39 DEGREES 57' 42.2" W 109 DEGREES 20' 38.7" ELEV 5275'	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-37355
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: BONANZA 1023-8H
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2619 FNL 0799 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 08 Township: 10.0S Range: 23.0E Meridian: S		9. API NUMBER: 43047382220000
PHONE NUMBER: 720 929-6515 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER	
	OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY		
NAME (PLEASE PRINT) Gina Becker	PHONE NUMBER 720 929-6086	TITLE Regulatory Analyst II
SIGNATURE N/A	DATE 7/28/2011	

US ROCKIES REGION

Operation Summary Report

Well: BONANZA 1023-8H					Spud Date: 10/21/2007				
Project: UTAH-UINTAH			Site: BONANZA 1023-8H PAD				Rig Name No: MILES 2/2		
Event: ABANDONMENT			Start Date: 7/13/2011				End Date: 7/19/2011		
Active Datum: RKB @5,302.99ft (above Mean Sea Leve			UWI: BONANZA 1023-8H						
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation	
7/18/2011	7:00 - 7:30	0.50	ABAND	48		P		MIRU	
	7:30 - 18:00	10.50	ABAND	45		P		MIRU 1300# CSG-TBG, KILL WELL, 20 BBLS, TBG, 30 BBLS CSG, NDWH, NU BOP'S, TEST BOP'S, UNLAND TBG, RU PRS, SCAN TBG, STD BACK 102 STDS, LAY DWN BALANCE, RD PRS. RU JW WIRE LINE, PU GAUGE RING, RUN TO 6470', POOH, PU 10 K CBP, TIH SET CBP AT 6460', POOH, RD JW WIRE LINE, TIH 00 STDS, SWIFN PULLED TBG 231 JTS J-55, 180 JTS YB, 51JTS RED BAND	
								N39 DEGREES 57' 42.2" W 109 DEGREES 20' 38.7" ELEV 5275'	
7/19/2011	7:00 - 7:30	0.50	ABAND	48		P		CEMENTING	
	7:30 - 7:30	0.00	ABAND	51		P		RU PRO PETRO, BREAK CIRC, TEST CSG TO 500# 5 MIN, ALL CEMENT USED, CLASS G, YIELD 1.145, DENISTY 15.8#, 4.9 GW/SX, SET PLUG #1 ON TOP OF CBP, 6460', PUMP 2.6 BBLS FRESH WTR, 10 SX, 2 BBLS CEMENT, DISPLACE WITH 1 BBL FRESH 23.5 BBLS T-MAC, POOH LAY DWN 73 JTS ON TLR, TO 4125', PUMP 2.6 BBLS FRESH, 20 SX, 4.1 BBLS CEMENT, DISPLACE WITH 1 BBL FRESH, 13.5 BBLS T-MAC, RD PRO PETRO, POOH LAY DWN BALANCE OF TBG ON TLR, ND BOP'S, CALL FMC TO PULL WH, RDMO CALLED CDC JIM 9:45 AM.	
								N39 DEGREES 57' 42.2" W 109 DEGREES 20' 38.7" ELEV 5275'	

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

RECEIVED

FEB 01 2012

FORM APPROVED
OMB No. 1004-0137
Expires: July 31, 2010

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

5. Lease Serial No.
UTU373551a. Type of Well ☐ Oil Well ☒ Gas Well ☐ Dry ☐ Other
b. Type of Completion ☐ New Well ☐ Work Over ☐ Deepen ☐ Plug Back ☒ Diff. Resvr.
Other _____

6. If Indian, Allottee or Tribe Name

7. Unit or CA Agreement Name and No.

2. Name of Operator
KERR MCGEE OIL & GAS ONSHORE, Mail: JAIME.SCHARNOWSKE@ANADARKO.COM

Contact: JAIME L. SCHARNOWSKE

8. Lease Name and Well No.
BONANZA 1023-8H3. Address
PO BOX 173779
DENVER, CO 802173a. Phone No. (include area code)
Ph: 720-929-63049. API Well No.
43-047-38222

4. Location of Well (Report location clearly and in accordance with Federal requirements)*

At surface SENE 2619FNL 799FEL

At top prod interval reported below SENE 2619FNL 799FEL

At total depth SENE 2619FNL 799FEL

10. Field and Pool, or Exploratory
NATURAL BUTTES11. Sec., T., R., M., or Block and Survey
or Area Sec 8 T10S R23E Mer SLB12. County or Parish
UINTAH13. State
UT14. Date Spudded
09/14/200715. Date T.D. Reached
10/28/200716. Date Completed
☐ D & A ☒ Ready to Prod.
11/21/201117. Elevations (DF, KB, RT, GL)*
5285 GL18. Total Depth: MD 8030
TVD19. Plug Back T.D.: MD 7978
TVD20. Depth Bridge Plug Set: MD
TVD21. Type Electric & Other Mechanical Logs Run (Submit copy of each)
CBL/CCL/GR-SD/DSN/ACTR22. Was well cored? ☒ No ☐ Yes (Submit analysis)
Was DST run? ☒ No ☐ Yes (Submit analysis)
Directional Survey? ☒ No ☐ Yes (Submit analysis)

23. Casing and Liner Record (Report all strings set in well)

Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sk. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled

24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)
2.375	7316							

25. Producing Intervals

26. Perforation Record

Formation	Top	Bottom	Perforated Interval	Size	No. Holes	Perf. Status
A) WASATCH	5258	5946	5258 TO 5946	0.360	69	OPEN
B) MESAVERDE	6530	7935	6530 TO 7935	0.360	167	OPEN
C)						
D)						

27. Acid, Fracture, Treatment, Cement Squeeze, Etc.

Depth Interval	Amount and Type of Material
5258 TO 5946	PUMP 3,345 BBLs SLICK H2O & 120,914 LBS 30/50 OTTAWA SAND

28. Production - Interval A

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
11/21/2011	11/27/2011	24	→	0.0	859.0	80.0			FLows FROM WELL
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
20/64	586	849.0	→	0	859	80		PGW	

28a. Production - Interval B

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
			→						

(See Instructions and spaces for additional data on reverse side)

ELECTRONIC SUBMISSION #129061 VERIFIED BY THE BLM WELL INFORMATION SYSTEM

** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED **

28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
			→						

28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
			→						

29. Disposition of Gas(Sold, used for fuel, vented, etc.)
SOLD

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top Meas. Depth
				GREEN RIVER BIRD'S NEST MAHOGANY WASATCH MESAVARDE	1105 1314 1688 4024 6060

32. Additional remarks (include plugging procedure):

Attached is the chronological recompletion history and perforation report.
Test information is production from Wasatch/Mesaverde perforations. Casing in the well is as previously reported on the original Completion Report.

33. Circle enclosed attachments:

- | | | | |
|---|--------------------|---------------|-----------------------|
| 1. Electrical/Mechanical Logs (1 full set req'd.) | 2. Geologic Report | 3. DST Report | 4. Directional Survey |
| 5. Sundry Notice for plugging and cement verification | 6. Core Analysis | 7. Other: | |

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions):

Electronic Submission #129061 Verified by the BLM Well Information System.
For KERR MCGEE OIL & GAS ONSHORE,L, sent to the Vernal

Name (please print) JAIME L. SCHARNOWSKE

Title REGULATORY ANALYST

Signature (Electronic Submission)

Date 01/24/2012

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL **

US ROCKIES REGION
Operation Summary Report

Well: BONANZA 1023-8H

Spud Date: 10/21/2007

Project: UTAH-UINTAH

Site: BONANZA 1023-8H PAD

Rig Name No: MILES 2/2, GWS 1/1

Event: RECOMPL/RESEREVEADD

Start Date: 10/25/2011

End Date: 11/21/2011

Active Datum: RKB @5,302.99usft (above Mean Sea Level)

UWI: BONANZA 1023-8H

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
10/25/2011	14:00 - 17:00	3.00	COMP	44		P		MIRU
10/26/2011	7:00 - 7:30	0.50	COMP	48		P		MILLING
	7:30 - 17:00	9.50	COMP	44		P		NU BOP'S, TALLY TBG, PU 3 7/8" BIT,BIT SUB, TIH TO 3876', MILL CEMENT PLUG, 256' , TIH TO 6253 197 JTS' TOC CBP, BREAK CIRC, CIRC CLEAN, POOH, LAY DWN TBG ON TLR, ND BOP'S, RDMO FILL SURFACE CSG. MIRU B&C QUICK TEST. PSI TEST T/ 1000 PSI. HELD FOR 15 MIN LOST 16 PSI. PSI TEST T/ 3500 PSI. HELD FOR 15 MIN LOST 63 PSI. 1ST PSI TEST T/ 7000 PSI. HELD FOR 30 MIN LOST 77 PSI. NO COMMUNICATION WITH SURFACE CSG BLEED OFF PSI. MOVE T/ NEXT WELL. SWIFWE
10/27/2011	12:00 - 16:00	4.00	COMP	33		P		

US ROCKIES REGION
Operation Summary Report

Well: BONANZA 1023-8H

Spud Date: 10/21/2007

Project: UTAH-UINTAH

Site: BONANZA 1023-8H PAD

Rig Name No: MILES 2/2, GWS 1/1

Event: RECOMPL/RESEREVEADD

Start Date: 10/25/2011

End Date: 11/21/2011

Active Datum: RKB @5,302.99usft (above Mean Sea Level)

UWI: BONANZA 1023-8H

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
11/4/2011	7:00 - 15:00	8.00	COMP	36	E	P		<p>PERF & FRAC FOLLOWING WELL AS PER DESIGN W/ 30/50 MESH SAND & SLK WTR. ALL CBP'S ARE HALIBURTON 8K CBP'S. REFER TO STIM PJR FOR FLUID, SAND AND CHEMICAL VOLUME PUMP'D</p> <p>PERF STG #1] P/U RIH, PERF WASATCH USING 3-1/8 EXPEND, 23 GRM, 0.36" HOLE. AS PERSAY IN PROCEDURE, X OVER TO FRAC CREW</p> <p>FRAC STG #1] WHP=350#, BRK DN PERFS=3,274#, @=4.5 BPM, INJ RT=49.4, INJ PSI=5,287#, INITIAL ISIP=1,431#, INITIAL FG=.68, FINAL ISIP=2,602#, FINAL FG=.89, AVERAGE RATE=49.3, AVERAGE PRESSURE=5,097#, MAX RATE=50.3, MAX PRESSURE=5,753#, NET PRESSURE INCREASE=1,171#, 16/24 67% CALC PERFS OPEN. X OVER TO WIRE LINE</p> <p>PERF STG #2] P/U RIH W/ HALIBURTON 8K CBP & PERF GUN, SET CBP @=5,690', PERF MESAVERDE USING 3-1/8 EXPEND, 23 GRM, 0.36" HOLE. AS PERSAY IN PROCEDURE, X OVER TO FRAC CREW</p> <p>FRAC STG #2] WHP=350#, BRK DN PERFS=2,421#, @=3.8 BPM, INJ RT=50.2, INJ PSI=4,174#, INITIAL ISIP=1,490#, INITIAL FG=.71, FINAL ISIP=1,763#, FINAL FG=.75, AVERAGE RATE=50.2, AVERAGE PRESSURE=3,800#, MAX RATE=50.9, MAX PRESSURE=4,656#, NET PRESSURE INCREASE=265#, 21/24 87% CALC PERFS OPEN. X OVER TO WIRE LINE</p> <p>PERF STG #3] P/U RIH W/ HALIBURTON 8K CBP & PERF GUN, SET CBP @=5,480', PERF MESAVERDE USING 3-1/8 EXPEND, 23 GRM, 0.36" HOLE. AS PERSAY IN PROCEDURE, X OVER TO FRAC CREW</p> <p>FRAC STG #3] WHP=566#, BRK DN PERFS=2,070#, @=3.9 BPM, INJ RT=50, INJ PSI=4,228#, INITIAL ISIP=1,166#, INITIAL FG=.66, FINAL ISIP=#, FINAL FG=., AVERAGE RATE=, AVERAGE PRESSURE=#, MAX RATE=, MAX PRESSURE=#, NET PRESSURE INCREASE=#, 19/24 89% CALC PERFS OPEN. X OVER TO WIRE LINE</p> <p>P/U RIH W/ HALIBURTON 8K CBP, SET FOR TOP KILL @=5,208'</p> <p>TOTAL FLUID PUMP'D=3,345 BBLS TOTAL SAND PUMP'D=120,914# HSM, SLIPS, TRIPS & FALLS, PU TBG</p>
11/17/2011	7:00 - 7:15	0.25	COMP	48		P		

US ROCKIES REGION
Operation Summary Report

Well: BONANZA 1023-8H

Spud Date: 10/21/2007

Project: UTAH-UINTAH

Site: BONANZA 1023-8H PAD

Rig Name No: MILES 2/2, GWS 1/1

Event: RECOMPL/RESEREVEADD

Start Date: 10/25/2011

End Date: 11/21/2011

Active Datum: RKB @5,302.99usft (above Mean Sea Level)

UWI: BONANZA 1023-8H

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	7:15 - 17:30	10.25	COMP	31	I	P		MIRU, ND WH, NU BOP, RU FLOOR & TBG EQUIP, PU 3 7/8" MILL & PUMP OPEN SUB, PU TBG, REMOVE THREAD PROTECTORS, RATTLE TBG, TALLY & DRIFT TBG, PRESS TEST BOP, SURFACE CSG VALVE OPEN & LOCKED, START DRLG PLUGS.
								C/O 25' SAND, TAG 1ST PLUG @ 5,208' DRL PLUG IN 10 MIN. 0 PSI INCREASE RIH, CSG PRESS 0 PSI. WOULD NOT FLOW W/O PUMPING.
								C/O 30' SAND, TAG 2ND PLUG @ 5,480' DRL PLUG IN 12 MIN. 0 PSI INCREASE RIH, CSG PRESS 0 PSI. WOULD NOT FLOW W/O PUMPING.
								C/O 25' SAND, TAG 3RD PLUG @ 5,690' DRL PLUG IN 15 MIN. 700 PSI INCREASE RIH, CSG PRESS 50 PSI.
								ISOLATION CBP & TOC @ 6,253', BTM PERF @ 5,946', RIH TO 5,745' W/ 183 JTS 2 3/8" J-55 TBG TO MAKE SURE PLUG WAS GONE, CIRC HOLE FOR 20 MIN, LD 10JTS EOT @ 5,426.67', WELL DIED, INSTAL TIW VALVE & SWI TO BUILD PRESS OVERNIGHT, DRAIN UP & WINTERIZE EQUIP, SDFN.
11/18/2011	7:00 - 7:15	0.25	COMP	48		P		HSM, SLIPS, TRIPS & FALLS, TRIPPING TBG
	7:15 - 17:00	9.75	COMP	31	I	P		SICP 0 PSI, OPEN WELL DEAD, TALKED W/ MICHAEL SOLLEE DECIDED TO D/O ISOLATION PLUG, POOH L/D PUMP OPEN SUB & SN GAULDED, PU 3 7/8" BIT, POBS & SN, RIH W/ TBG TAG @ 6,245', RU P/S BREAK CIRC W/ RIG PUMP, D/O CMT & ISOLATION PLUG FROM 6,245' TO 6,460' WELL WENT ON VACUMN, RIH W/ TBG TAGGED UP @ 7,340', WILL C/O TO BTM W/ AIR FOAM MONDAY, SWI, DRAIN & WINTERIZE EQUIP, SDFWE.
11/21/2011	7:00 - 7:15	0.25	COMP	48		P		HSM, SLIPS, TRIPS & FALLS, RIGGING UP & DOWN, IN WET WEATHER

US ROCKIES REGION
Operation Summary Report

Well: BONANZA 1023-8H

Spud Date: 10/21/2007

Project: UTAH-UINTAH

Site: BONANZA 1023-8H PAD

Rig Name No: MILES 2/2, GWS 1/1

Event: RECOMPL/RESEREVEADD

Start Date: 10/25/2011

End Date: 11/21/2011

Active Datum: RKB @5,302.99usft (above Mean Sea Level)

UWI: BONANZA 1023-8H

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	7:15 - 17:00	9.75	COMP	44	D	P		<p>SICP 200 PSI, INSTAL STRING FLOAT, OPEN WELL BLEW DEAD RIGHT AWAY NO FLUID BACK, BREAK CIRC W/ AIR FOAM & N2 UNIT, C/O FROM 7,340' TO 7,410' FELL FREE RIH TAGGED @ 7,960', C/O FROM 7,960' TO 7,970' ON OLD POBS, PBTB @ 7,978' BTM PERF @ 7,935', 35' PAST BTM PERF W/ 252 JTS 2 3/8" J-55 TBG, CIRC HOLE FOR 20 MIN, PUMP 10 BBLS TO KILL TBG TO REMOVE STRING FLOAT, SET P/S BACK, LD 20 JTS, PU & STRIP IN TBG HANGER & LAND TBG W/ 232 JTS 2 3/8" J-55, EOT @ 7,315.87'.</p> <p>RD POWER SWIVEL, FLOOR & TBG EQUIP, ND BOPS, NU WH, DROP BALL TO SHEAR OFF BIT W/ 2,400 PSI, LET BIT FALL FOR 20 MIN.</p> <p>UNHOOK HAL 9000 LINES TO MOVE EQUIP & HOOK BACK UP.</p> <p>TURN OVER TO FLOW BACK CREW, RD & MOVE TO BONANZA 1023-8I PAD.</p> <p>KB= 18' 185 JTS B&C YARD // 70 JTS SAMUELS YARD 4 1/16" WEATHERFORD HANGER= .83' TOTAL TBG DELIVERED 255 JTS YELLOW BAND 232 JTS 2 3/8" J-55 = 7,294.84' TBG USED 232 JTS YELLOW BAND J-55 POBS= 2.20' TBG RETURNED 23 JTS TO SAMUELS YARD EOT @ 7, 315.87'</p> <p>TWTR= 3,345 BBLS TWR= 1,000 BBLS TWLTR= 2,345 BBLS WELL IP'D ON 11/27/11 - 859 MCFD, 0 BOPD, 80 BWPD, CP 849#, FTP 586#, CK 20/64", LP 68#, 24 HRS</p>
11/27/2011	7:00 -		PROD	50				

1 General

1.1 Customer Information

Company	US ROCKIES REGION
Representative	
Address	

1.2 Well/Wellbore Information

Well	BONANZA 1023-8H	Wellbore No.	OH
Well Name	BONANZA 1023-8H	Wellbore Name	BONANZA 1023-8H
Report No.	1	Report Date	10/25/2011
Project	UTAH-UINTAH	Site	BONANZA 1023-8H PAD
Rig Name/No.	MILES 2/2	Event	RECOMPL/RESERVEADD
Start Date	10/25/2011	End Date	11/21/2011
Spud Date	10/21/2007	Active Datum	RKB @5,302.99usft (above Mean Sea Level)
UWI	BONANZA 1023-8H		

1.3 General

Contractor	CASED HOLE SOLUTIONS	Job Method	PERFORATE	Supervisor	ED GUDAC
Perforated Assembly	PRODUCTION CASING	Conveyed Method	WIRELINE		

1.4 Initial Conditions

Fluid Type		Fluid Density		Gross Interval	5,258.0 (usft)-5,946.0 (usft)	Start Date/Time	10/28/2011 12:00AM
Surface Press		Estimate Res Press		No. of Intervals	9	End Date/Time	10/28/2011 12:00AM
TVD Fluid Top		Fluid Head		Total Shots	0	Net Perforation Interval	19.00 (usft)
Hydrostatic Press		Press Difference		Avg Shot Density	0.00 (shot/ft)	Final Surface Pressure	
Balance Cond	NEUTRAL					Final Press Date	

1.5 Summary

2 Intervals

2.1 Perforated Interval


Date	Formation/ Reservoir	CCL@ (usft)	CCL-T S (usft)	MD Top (usft)	MD Base (usft)	Shot Density (shot/ft)	Misfires/ Add. Shot	Diameter (in)	Carr Type /Carr Manuf	Carr Size (in)	Phasing (°)	Charge Desc /Charge Manufacturer	Charge Weight (gram)	Reason	Misrun
10/28/2011 12:00AM	WASATCH/ 1			5,258.0	5,259.0			0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	

2.1 Perforated Interval (Continued)

Date	Formation/ Reservoir	CCL@ (usft)	CCL-T S (usft)	MD Top (usft)	MD Base (usft)	Shot Density (shot/ft)	Misfires/ Add. Shot	Diamete r (in)	Carr Type /Carr Manuf	Carr Size (in)	Phasing (°)	Charge Desc /Charge Manufacturer	Charge Weight (gram)	Reason	Misrun
10/28/2011 12:00AM	WASATCH/			5,292.0	5,294.0			0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/28/2011 12:00AM	WASATCH/			5,373.0	5,374.0			0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/28/2011 12:00AM	WASATCH/			5,421.0	5,422.0			0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/28/2011 12:00AM	WASATCH/			5,448.0	5,450.0			0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/28/2011 12:00AM	WASATCH/			5,571.0	5,573.0			0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
10/28/2011 12:00AM	WASATCH/			5,656.0	5,660.0			0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
10/28/2011 12:00AM	WASATCH/			5,894.0	5,897.0			0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
10/28/2011 12:00AM	WASATCH/			5,943.0	5,946.0			0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	

3 Plots

3.1 Wellbore Schematic



STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: KERR MCGEE OIL & GAS ONSHORE LP Operator Account Number: N 2995
Address: 1368 SOUTH 1200 EAST
city VERNAL
state UT zip 84078 Phone Number: (435) 781-7024

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304738237	BONANZA 1023-17C		NENW	17	10S	23E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
E	16585	16585				11/17/2011	
Comments: THE SUBJECT WELL WAS RECOMPLETED INTO A NEW FORMATION. CHANGE FROM WASATCH TO WASATCH/MESAVERDE FORMATION EFFECTIVE 11/17/2011. — 2123120R							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304738222	BONANZA 1023-8H		SENE	8	10S	23E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
E	16353	16353				11/21/2011	
Comments: THE SUBJECT WELL WAS RECOMPLETED INTO A NEW FORMATION. CHANGE FROM WASATCH TO WASATCH/MESAVERDE FORMATION EFFECTIVE 11/21/2011. — 2123120R							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

SHEILA WOPSOCK

Name (Please Print)

Signature

REGULATORY ANALYST

Title

2/16/2012

Date

(5/2000)

RECEIVED

FEB 16 2012

Oil, Gas & Mining

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: KERR MCGEE OIL & GAS ONSHORE LP Operator Account Number: N 2995
Address: P.O. Box 173779
city DENVER
state CO zip 80217 Phone Number: (720) 929-6029

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
See Atchmt	See Atchmt						
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
	99999	18519				5/11/2012	
Comments: Please see attachment with list of Wells in the Ponderosa Unit. <u>WSMVD</u> 5/30/2012							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

RECEIVED

MAY 21 2012

Div. of Oil, Gas & Mining

Cara Mahler

Name (Please Print)

Signature

REGULATORY ANALYST

Title

5/21/2012

Date

well_name	sec	tpw	rng	api	entity		lease	well	stat	qtr_qtr	bhl	surf	zone	a_stat	l_num	op_no
SOUTHMAN CANYON 31-3	31	090S	230E	4304734726	13717		1	GW	P	SENW		1	WSMVD	P	U-33433	N2995
SOUTHMAN CANYON 31-4	31	090S	230E	4304734727	13742		1	GW	S	SESW		1	WSMVD	S	UTU-33433	N2995
SOUTHMAN CYN 31-2X (RIG SKID)	31	090S	230E	4304734898	13755		1	GW	P	NWNW		1	WSMVD	P	U-33433	N2995
SOUTHMAN CYN 923-31J	31	090S	230E	4304735149	13994		1	GW	P	NWSE		1	MVRD	P	U-33433	N2995
SOUTHMAN CYN 923-31B	31	090S	230E	4304735150	13953		1	GW	P	NWNE		1	MVRD	P	U-33433	N2995
SOUTHMAN CYN 923-31P	31	090S	230E	4304735288	14037		1	GW	P	SESE		1	WSMVD	P	UTU-33433	N2995
SOUTHMAN CYN 923-31H	31	090S	230E	4304735336	14157		1	GW	P	SENE		1	WSMVD	P	U-33433	N2995
SOUTHMAN CYN 923-31O	31	090S	230E	4304737205	16827		1	GW	P	SWSE		1	MVRD	P	UTU-33433	N2995
SOUTHMAN CYN 923-31K	31	090S	230E	4304737206	16503		1	GW	P	NESW		1	WSMVD	P	UTU-33433	N2995
SOUTHMAN CYN 923-31G	31	090S	230E	4304737208	16313		1	GW	P	SWNE		1	WSMVD	P	UTU-33433	N2995
SOUTHMAN CYN 923-31E	31	090S	230E	4304737209	16521		1	GW	P	SWNW		1	WSMVD	P	UTU-33433	N2995
SOUTHMAN CYN 923-31A	31	090S	230E	4304737210	16472		1	GW	P	NENE		1	WSMVD	P	UTU-33433	N2995
SOUTHMAN CYN 923-31C	31	090S	230E	4304737227	16522		1	GW	P	NENW		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-1G	01	100S	230E	4304735512	14458		1	GW	P	SWNE		1	WSMVD	P	U-40736	N2995
BONANZA 1023-1A	01	100S	230E	4304735717	14526		1	GW	P	NENE		1	WSMVD	P	U-40736	N2995
BONANZA 1023-1E	01	100S	230E	4304735745	14524		1	GW	P	SWNW		1	WSMVD	P	U-40736	N2995
BONANZA 1023-1C	01	100S	230E	4304735754	14684		1	GW	P	NENW		1	MVRD	P	U-40736	N2995
BONANZA 1023-1K	01	100S	230E	4304735755	15403		1	GW	P	NESW		1	MVRD	P	U-38423	N2995
BONANZA 1023-1F	01	100S	230E	4304737379	16872		1	GW	P	SENW		1	MVRD	P	UTU-40736	N2995
BONANZA 1023-1B	01	100S	230E	4304737380	16733		1	GW	P	NWNE		1	MVRD	P	UTU-40736	N2995
BONANZA 1023-1D	01	100S	230E	4304737381	16873		1	GW	P	NWNW		1	MVRD	P	UTU-40736	N2995
BONANZA 1023-1H	01	100S	230E	4304737430	16901		1	GW	P	SENE		1	MVRD	P	UTU-40736	N2995
BONANZA 1023-1L	01	100S	230E	4304738300	16735		1	GW	P	NWSW		1	MVRD	P	UTU-38423	N2995
BONANZA 1023-1J	01	100S	230E	4304738302	16871		1	GW	P	NWSE		1	MVRD	P	UTU-40736	N2995
BONANZA 1023-1I	01	100S	230E	4304738810	16750		1	GW	P	NESE		1	MVRD	P	UTU-40736	N2995
BONANZA 1023-2E	02	100S	230E	4304735345	14085		3	GW	P	SWNW		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2C	02	100S	230E	4304735346	14084		3	GW	P	NENW		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2A	02	100S	230E	4304735347	14068		3	GW	P	NENE		3	MVRD	P	ML-47062	N2995
BONANZA 1023-2G	02	100S	230E	4304735661	14291		3	GW	P	SWNE		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2O	02	100S	230E	4304735662	14289		3	GW	P	SWSE		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2I	02	100S	230E	4304735663	14290		3	GW	S	NESE		3	WSMVD	S	ML-47062	N2995
BONANZA 1023-2MX	02	100S	230E	4304736092	14730		3	GW	P	SWSW		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2H	02	100S	230E	4304737093	16004		3	GW	P	SENE		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2D	02	100S	230E	4304737094	15460		3	GW	P	NWNW		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2B	02	100S	230E	4304737095	15783		3	GW	P	NWNE		3	MVRD	P	ML-47062	N2995
BONANZA 1023-2P	02	100S	230E	4304737223	15970		3	GW	P	SESE		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2N	02	100S	230E	4304737224	15887		3	GW	P	SESW		3	MVRD	P	ML-47062	N2995
BONANZA 1023-2L	02	100S	230E	4304737225	15833		3	GW	P	NWSW		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2F	02	100S	230E	4304737226	15386		3	GW	P	SENW		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2D-4	02	100S	230E	4304738761	16033		3	GW	P	NWNW		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2O-1	02	100S	230E	4304738762	16013		3	GW	P	SWSE		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2H3CS	02	100S	230E	4304750344	17426		3	GW	P	NWNE	D	3	MVRD	P	ML 47062	N2995
BONANZA 1023-2G3BS	02	100S	230E	4304750345	17428		3	GW	P	NWNE	D	3	MVRD	P	ML 47062	N2995
BONANZA 1023-2G2CS	02	100S	230E	4304750346	17429		3	GW	P	NWNE	D	3	MVRD	P	ML 47062	N2995
BONANZA 1023-2G1BS	02	100S	230E	4304750347	17427		3	GW	P	NWNE	D	3	MVRD	P	ML 47062	N2995

BONANZA 1023-2M1S	02	100S	230E	4304750379	17443		3	GW	P	SENW	D	3	MVRD	P	ML 47062	N2995
BONANZA 1023-2L2S	02	100S	230E	4304750380	17444		3	GW	P	SENW	D	3	MVRD	P	ML 47062	N2995
BONANZA 1023-2K4S	02	100S	230E	4304750381	17446		3	GW	P	SENW	D	3	MVRD	P	ML 47062	N2995
BONANZA 1023-2K1S	02	100S	230E	4304750382	17445		3	GW	P	SENW	D	3	WSMVD	P	ML 47062	N2995
BONANZA 4-6 ✱	04	100S	230E	4304734751	13841		1	GW	P	NESW		1	MNCS	P	UTU-33433	N2995
BONANZA 1023-4A	04	100S	230E	4304735360	14261		1	GW	P	NENE		1	WSMVD	P	U-33433	N2995
BONANZA 1023-4E	04	100S	230E	4304735392	14155		1	GW	P	SWNW		1	WSMVD	P	U-33433	N2995
BONANZA 1023-4C	04	100S	230E	4304735437	14252		1	GW	P	NENW		1	WSMVD	P	U-33433	N2995
BONANZA 1023-4M	04	100S	230E	4304735629	14930		1	GW	P	SWSW		1	WSMVD	P	U-33433	N2995
BONANZA 1023-4O	04	100S	230E	4304735688	15111		1	GW	P	SWSE		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-4I	04	100S	230E	4304735689	14446		1	GW	P	NESE		1	MVRD	P	UTU-33433	N2995
BONANZA 1023-4G	04	100S	230E	4304735746	14445		1	GW	P	SWNE		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-4D	04	100S	230E	4304737315	16352		1	GW	P	NWNW		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-4H	04	100S	230E	4304737317	16318		1	GW	P	SENE		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-4B	04	100S	230E	4304737328	16351		1	GW	P	NWNE		1	MVRD	P	UTU-33433	N2995
BONANZA 1023-4L	04	100S	230E	4304738211	16393		1	GW	P	NWSW		1	MVRD	P	UTU-33433	N2995
BONANZA 1023-4P	04	100S	230E	4304738212	16442		1	GW	P	SESE		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-4N	04	100S	230E	4304738303	16395		1	GW	P	SESW		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-4FX (RIGSKID)	04	100S	230E	4304739918	16356		1	GW	P	SENW		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-5O	05	100S	230E	4304735438	14297		1	GW	P	SWSE		1	WSMVD	P	U-33433	N2995
BONANZA 1023-5AX (RIGSKID)	05	100S	230E	4304735809	14243		1	GW	P	NENE		1	WSMVD	P	U-33433	N2995
BONANZA 1023-5C	05	100S	230E	4304736176	14729		1	GW	P	NENW		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-5G	05	100S	230E	4304736177	14700		1	GW	P	SWNE		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-5M	05	100S	230E	4304736178	14699		1	GW	P	SWSW		1	WSMVD	P	UTU-73450	N2995
BONANZA 1023-5K	05	100S	230E	4304736741	15922		1	GW	P	NESW		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-5B	05	100S	230E	4304737318	16904		1	GW	P	NWNE		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-5E	05	100S	230E	4304737319	16824		1	GW	P	SWNW		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-5H	05	100S	230E	4304737320	16793		1	GW	P	SENE		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-5N	05	100S	230E	4304737321	16732		1	GW	P	SESW		1	WSMVD	P	UTU-73450	N2995
BONANZA 1023-5L	05	100S	230E	4304737322	16825		1	GW	P	NWSW		1	MVRD	P	UTU-33433	N2995
BONANZA 1023-5J	05	100S	230E	4304737428	17055		1	GW	P	NWSE		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-5P	05	100S	230E	4304738213	16795		1	GW	P	SESE		1	MVRD	P	UTU-33433	N2995
BONANZA 1023-5N-1	05	100S	230E	4304738911	17060		1	GW	P	SESW		1	WSMVD	P	UTU-73450	N2995
BONANZA 1023-5PS	05	100S	230E	4304750169	17323		1	GW	P	NESE	D	1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-5G2AS	05	100S	230E	4304750486	17459		1	GW	P	SWNE	D	1	MVRD	P	UTU 33433	N2995
BONANZA 1023-5G2CS	05	100S	230E	4304750487	17462		1	GW	P	SWNE	D	1	MVRD	P	UTU 33433	N2995
BONANZA 1023-5G3BS	05	100S	230E	4304750488	17461		1	GW	P	SWNE	D	1	MVRD	P	UTU 33433	N2995
BONANZA 1023-5G3CS	05	100S	230E	4304750489	17460		1	GW	P	SWNE	D	1	MVRD	P	UTU 33433	N2995
BONANZA 1023-5N4AS	05	100S	230E	4304752080	18484		1	GW	DRL	SWSW	D	1	WSMVD	DRL	UTU73450	N2995
BONANZA 1023-8C2DS	05	100S	230E	4304752081	18507		1	GW	DRL	SWSW	D	1	WSMVD	DRL	UTU37355	N2995
BONANZA 6-2	06	100S	230E	4304734843	13796		1	GW	TA	NESW		1	WSMVD	TA	UTU-38419	N2995
BONANZA 1023-6C	06	100S	230E	4304735153	13951		1	GW	P	NENW		1	MVRD	P	U-38419	N2995
BONANZA 1023-6E	06	100S	230E	4304735358	14170		1	GW	P	SWNW		1	MVRD	P	U-38419	N2995
BONANZA 1023-6M	06	100S	230E	4304735359	14233		1	GW	P	SWSW		1	WSMVD	P	U-38419	N2995
BONANZA 1023-6G	06	100S	230E	4304735439	14221		1	GW	P	SWNE		1	WSMVD	P	UTU-38419	N2995
BONANZA 1023-6O	06	100S	230E	4304735630	14425		1	GW	TA	SWSE		1	WSMVD	TA	U-38419	N2995

✱ not moved in unit

BONANZA 1023-6A	06	100S	230E	4304736067	14775		1	GW	P	NENE		1	WSMVD	P	U-33433	N2995
BONANZA 1023-6N	06	100S	230E	4304737211	15672		1	GW	P	SESW		1	WSMVD	P	UTU-38419	N2995
BONANZA 1023-6L	06	100S	230E	4304737212	15673		1	GW	P	NWSW		1	WSMVD	P	UTU-38419	N2995
BONANZA 1023-6J	06	100S	230E	4304737213	15620		1	GW	P	NWSE		1	WSMVD	P	UTU-38419	N2995
BONANZA 1023-6F	06	100S	230E	4304737214	15576		1	GW	TA	SENW		1	WSMVD	TA	UTU-38419	N2995
BONANZA 1023-6P	06	100S	230E	4304737323	16794		1	GW	P	SESE		1	WSMVD	P	UTU-38419	N2995
BONANZA 1023-6H	06	100S	230E	4304737324	16798		1	GW	S	SENE		1	WSMVD	S	UTU-33433	N2995
BONANZA 1023-6D	06	100S	230E	4304737429	17020		1	GW	P	NWNW		1	WSMVD	P	UTU-38419	N2995
BONANZA 1023-6B	06	100S	230E	4304740398	18291		1	GW	P	NWNE		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-6M1BS	06	100S	230E	4304750452	17578		1	GW	P	NWSW	D	1	WSMVD	P	UTU 38419	N2995
BONANZA 1023-6N1AS	06	100S	230E	4304750453	17581		1	GW	P	NWSW	D	1	WSMVD	P	UTU 38419	N2995
BONANZA 1023-6N1CS	06	100S	230E	4304750454	17580		1	GW	P	NWSW	D	1	WSMVD	P	UTU 38419	N2995
BONANZA 1023-6N4BS	06	100S	230E	4304750455	17579		1	GW	P	NWSW	D	1	WSMVD	P	UTU 38419	N2995
BONANZA 1023-6I2S	06	100S	230E	4304750457	17790		1	GW	P	NESE	D	1	WSMVD	P	UTU 38419	N2995
BONANZA 1023-6I4S	06	100S	230E	4304750458	17792		1	GW	P	NESE	D	1	WSMVD	P	UTU 38419	N2995
BONANZA 1023-6J3S	06	100S	230E	4304750459	17791		1	GW	P	NESE	D	1	WSMVD	P	UTU 38419	N2995
BONANZA 1023-6P1S	06	100S	230E	4304750460	17793		1	GW	P	NESE	D	1	WSMVD	P	UTU 38419	N2995
BONANZA 1023-6A2CS	06	100S	230E	4304751430	18292		1	GW	P	NWNE	D	1	WSMVD	P	UTU33433	N2995
BONANZA 1023-6B4BS	06	100S	230E	4304751431	18293		1	GW	P	NWNE	D	1	WSMVD	P	UTU33433	N2995
BONANZA 1023-6B4CS	06	100S	230E	4304751432	18294		1	GW	P	NWNE	D	1	WSMVD	P	UTU33433	N2995
BONANZA 1023-6C4BS	06	100S	230E	4304751449	18318		1	GW	P	NENW	D	1	WSMVD	P	UTU38419	N2995
BONANZA 1023-6D1DS	06	100S	230E	4304751451	18316		1	GW	P	NENW	D	1	WSMVD	P	UTU38419	N2995
FLAT MESA FEDERAL 2-7	07	100S	230E	4304730545	18244		1	GW	S	NENW		1	WSMVD	S	U-38420	N2995
BONANZA 1023-7B	07	100S	230E	4304735172	13943		1	GW	P	NWNE		1	MVRD	P	U-38420	N2995
BONANZA 1023-7L	07	100S	230E	4304735289	14054		1	GW	P	NWSW		1	WSMVD	P	U-38420	N2995
BONANZA 1023-7D	07	100S	230E	4304735393	14171		1	GW	P	NWNW		1	WSMVD	P	U-38420	N2995
BONANZA 1023-7P	07	100S	230E	4304735510	14296		1	GW	P	SESE		1	WSMVD	P	U-38420	N2995
BONANZA 1023-7H	07	100S	230E	4304736742	15921		1	GW	P	SENE		1	WSMVD	P	UTU-38420	N2995
BONANZA 1023-7NX (RIGSKID)	07	100S	230E	4304736932	15923		1	GW	P	SESW		1	WSMVD	P	UTU-38420	N2995
BONANZA 1023-7M	07	100S	230E	4304737215	16715		1	GW	P	SWSW		1	WSMVD	P	UTU-38420	N2995
BONANZA 1023-7K	07	100S	230E	4304737216	16714		1	GW	P	NESW		1	WSMVD	P	UTU-38420	N2995
BONANZA 1023-7E	07	100S	230E	4304737217	16870		1	GW	P	SWNW		1	WSMVD	P	UTU-38420	N2995
BONANZA 1023-7G	07	100S	230E	4304737326	16765		1	GW	P	SWNE		1	WSMVD	P	UTU-38420	N2995
BONANZA 1023-7A	07	100S	230E	4304737327	16796		1	GW	P	NENE		1	WSMVD	P	UTU-38420	N2995
BONANZA 1023-7O	07	100S	230E	4304738304	16713		1	GW	P	SWSE		1	MVRD	P	UTU-38420	N2995
BONANZA 1023-7B-3	07	100S	230E	4304738912	17016		1	GW	P	NWNE		1	WSMVD	P	UTU-38420	N2995
BONANZA 1023-07JT	07	100S	230E	4304739390	16869		1	GW	P	NWSE		1	WSMVD	P	UTU-38420	N2995
BONANZA 1023-7J2AS	07	100S	230E	4304750474	17494		1	GW	P	NWSE	D	1	WSMVD	P	UTU 38420	N2995
BONANZA 1023-7J2DS	07	100S	230E	4304750475	17495		1	GW	P	NWSE	D	1	WSMVD	P	UTU 38420	N2995
BONANZA 1023-7L3DS	07	100S	230E	4304750476	17939		1	GW	P	NWSW	D	1	WSMVD	P	UTU 38420	N2995
BONANZA 1023-7M2AS	07	100S	230E	4304750477	17942		1	GW	P	NWSW	D	1	WSMVD	P	UTU 38420	N2995
BONANZA 1023-7N2AS	07	100S	230E	4304750478	17940		1	GW	P	NWSW	D	1	WSMVD	P	UTU 38420	N2995
BONANZA 1023-7N2DS	07	100S	230E	4304750479	17941		1	GW	P	NWSW	D	1	WSMVD	P	UTU 38420	N2995
BONANZA 1023-7O4S	07	100S	230E	4304750480	17918		1	GW	P	SESE	D	1	WSMVD	P	UTU 38420	N2995
BONANZA 1023-7P2S	07	100S	230E	4304750482	17919		1	GW	P	SESE	D	1	WSMVD	P	UTU 38420	N2995
BONANZA 8-2	08	100S	230E	4304734087	13851		1	GW	P	SESE		1	MVRD	P	U-37355	N2995

BONANZA 8-3	08	100S	230E	4304734770	13843		1	GW	P	NWNW		1	MVRD	P	U-37355	N2995
BONANZA 1023-8A	08	100S	230E	4304735718	14932		1	GW	P	NENE		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8L	08	100S	230E	4304735719	14876		1	GW	P	NWSW		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8N	08	100S	230E	4304735720	15104		1	GW	P	SESW		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8F	08	100S	230E	4304735989	14877		1	GW	S	SENW		1	WSMVD	S	UTU-37355	N2995
BONANZA 1023-8I	08	100S	230E	4304738215	16358		1	GW	P	NESE		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8K	08	100S	230E	4304738216	16354		1	GW	P	NESW		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8M	08	100S	230E	4304738217	16564		1	GW	P	SWSW		1	MVRD	P	UTU-37355	N2995
BONANZA 1023-8G	08	100S	230E	4304738218	16903		1	GW	P	SWNE		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8E	08	100S	230E	4304738219	16397		1	GW	P	SWNW		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8C	08	100S	230E	4304738220	16355		1	GW	P	NENW		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8B	08	100S	230E	4304738221	16292		1	GW	P	NWNE		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8H	08	100S	230E	4304738222	16353		1	GW	P	SENE		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8O	08	100S	230E	4304738305	16392		1	GW	P	SWSE		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8B-4	08	100S	230E	4304738914	17019		1	GW	P	NWNE		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8A1DS	08	100S	230E	4304750481	17518		1	GW	P	NENE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8A4BS	08	100S	230E	4304750483	17519		1	GW	P	NENE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8B1AS	08	100S	230E	4304750484	17520		1	GW	P	NENE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8B2AS	08	100S	230E	4304750485	17521		1	GW	P	NENE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8O2S	08	100S	230E	4304750495	17511		1	GW	P	NWSE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8J1S	08	100S	230E	4304750496	17509		1	GW	P	NWSE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8O3S	08	100S	230E	4304750497	17512		1	GW	P	NWSE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8J3	08	100S	230E	4304750498	17510		1	GW	P	NWSE		1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8C4CS	08	100S	230E	4304750499	17544		1	GW	P	NENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8D2DS	08	100S	230E	4304750500	17546		1	GW	P	NENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8D3DS	08	100S	230E	4304750501	17545		1	GW	P	NENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8F3DS	08	100S	230E	4304750502	17543		1	GW	P	NENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8A4CS	08	100S	230E	4304751131	18169		1	GW	P	NWNE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8B3BS	08	100S	230E	4304751132	18167		1	GW	P	NWNE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8C1AS	08	100S	230E	4304751133	18166		1	GW	P	NWNE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8G3AS	08	100S	230E	4304751134	18168		1	GW	P	NWNE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8E2AS	08	100S	230E	4304751135	18227		1	GW	P	SENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8F3BS	08	100S	230E	4304751136	18227		1	GW	P	SENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8F4AS	08	100S	230E	4304751137	18224		1	GW	P	SENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8F4DS	08	100S	230E	4304751138	18225		1	GW	P	SENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8J2CS	08	100S	230E	4304751139	18226		1	GW	P	SENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8G4DS	08	100S	230E	4304751140	18144		1	GW	P	NESE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8H2DS	08	100S	230E	4304751141	18142		1	GW	P	NESE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8H3DS	08	100S	230E	4304751142	18143		1	GW	P	NESE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8H4DS	08	100S	230E	4304751143	18141		1	GW	P	NESE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8I4BS	08	100S	230E	4304751144	18155		1	GW	P	NESE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8J4BS	08	100S	230E	4304751145	18154		1	GW	P	NESE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8P1AS	08	100S	230E	4304751146	18156		1	GW	P	NESE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8P2BS	08	100S	230E	4304751147	18153		1	GW	P	NESE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8P4AS	08	100S	230E	4304751148	18157		1	GW	P	NESE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8E2DS	08	100S	230E	4304751149	18201		1	GW	P	NWSW	D	1	WSMVD	P	UTU 37355	N2995

BONANZA 1023-8E3DS	08	100S	230E	4304751150	18200		1	GW	P	NWSW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8K1CS	08	100S	230E	4304751151	18199		1	GW	P	NWSW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8K4CS	08	100S	230E	4304751152	18198		1	GW	P	NWSW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8L3DS	08	100S	230E	4304751153	18197		1	GW	P	NWSW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8M2AS	08	100S	230E	4304751154	18217		1	GW	P	SWSW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8M2DS	08	100S	230E	4304751155	18216		1	GW	P	SWSW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8N2BS	08	100S	230E	4304751156	18218		1	GW	P	SWSW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8O3CS	08	100S	230E	4304751157	18254		1	GW	P	SWSE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8N3DS	08	100S	230E	4304751158	18215		1	GW	P	SWSW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8O4AS	08	100S	230E	4304751159	18252		1	GW	P	SWSE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8P2CS	08	100S	230E	4304751160	18251		1	GW	P	SWSE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8P3CS	08	100S	230E	4304751161	18253		1	GW	P	SWSE	D	1	WSMVD	P	UTU 37355	N2995
CANYON FEDERAL 2-9	09	100S	230E	4304731504	1468		1	GW	P	NENW		1	MVRD	P	U-37355	N2995
SOUTHMAN CANYON 9-3-M	09	100S	230E	4304732540	11767		1	GW	S	SWSW		1	MVRD	S	UTU-37355	N2995
SOUTHMAN CANYON 9-4-J	09	100S	230E	4304732541	11685		1	GW	S	NWSE		1	MVRD	S	UTU-37355	N2995
BONANZA 9-6	09	100S	230E	4304734771	13852		1	GW	P	NWNE		1	MVRD	P	U-37355	N2995
BONANZA 9-5	09	100S	230E	4304734866	13892		1	GW	P	SESW		1	MVRD	P	U-37355	N2995
BONANZA 1023-9E	09	100S	230E	4304735620	14931		1	GW	P	SWNW		1	WSMVD	P	U-37355	N2995
BONANZA 1023-9I	09	100S	230E	4304738223	16766		1	GW	P	NESE		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-9D	09	100S	230E	4304738306	16398		1	GW	P	NWNW		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-9J	09	100S	230E	4304738811	16989		1	GW	P	NWSE		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-9B3BS	09	100S	230E	4304750503	17965		1	GW	P	SENE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-9B3CS	09	100S	230E	4304750504	17968		1	GW	P	SENE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-9H2BS	09	100S	230E	4304750505	17966		1	GW	P	SENE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-9H2CS	09	100S	230E	4304750506	17967		1	GW	P	SENE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 10-2	10	100S	230E	4304734704	13782		1	GW	P	NWNW		1	MVRD	P	U-72028	N2995
BONANZA 1023-10L	10	100S	230E	4304735660	15164		1	GW	P	NWSW		1	WSMVD	P	U-38261	N2995
BONANZA 1023-10E	10	100S	230E	4304738224	16501		1	GW	P	SWNW		1	MVRD	P	UTU-72028	N2995
BONANZA 1023-10C	10	100S	230E	4304738228	16500		1	GW	P	NENW		1	MVRD	P	UTU-72028	N2995
BONANZA 1023-10C-4	10	100S	230E	4304738915	17015		1	GW	P	NENW		1	MVRD	P	UTU-72028	N2995
BONANZA 11-2 ★	11	100S	230E	4304734773	13768		1	GW	P	SWNW		1	MVMCS	P	UTU-38425	N2995
BONANZA 1023-11K	11	100S	230E	4304735631	15132		1	GW	P	NESW		1	WSMVD	P	UTU-38425	N2995
BONANZA 1023-11B	11	100S	230E	4304738230	16764		1	GW	P	NWNE		1	MVRD	P	UTU-38425	N2995
BONANZA 1023-11F	11	100S	230E	4304738232	16797		1	GW	P	SENW		1	MVRD	P	UTU-38425	N2995
BONANZA 1023-11D	11	100S	230E	4304738233	16711		1	GW	P	NWNW		1	MVRD	P	UTU-38425	N2995
BONANZA 1023-11G	11	100S	230E	4304738235	16826		1	GW	P	SWNE		1	MVRD	P	UTU-38425	N2995
BONANZA 1023-11C	11	100S	230E	4304738309	16736		1	GW	P	NENW		1	MVRD	P	UTU-38425	N2995
BONANZA 1023-11J	11	100S	230E	4304738310	16839		1	GW	P	NWSE		1	WSMVD	P	UTU-38424	N2995
BONANZA 1023-11N	11	100S	230E	4304738311	16646		1	GW	P	SESW		1	MVRD	P	UTU-38424	N2995
BONANZA 1023-11M	11	100S	230E	4304738312	16687		1	GW	P	SWSW		1	MVRD	P	UTU-38424	N2995
BONANZA 1023-11L	11	100S	230E	4304738812	16987		1	GW	P	NWSW		1	WSMVD	P	UTU-38424	N2995
NSO FEDERAL 1-12	12	100S	230E	4304730560	1480		1	GW	P	NENW		1	MVRD	P	UTU-38423	N2995
WHITE RIVER 1-14	14	100S	230E	4304730481	1500		1	GW	S	NENW		1	MVRD	S	U-38427	N2995
BONANZA 1023-14D	14	100S	230E	4304737030	16799		1	GW	P	NWNW		1	MVRD	P	UTU-38427	N2995
BONANZA 1023-14C	14	100S	230E	4304738299	16623		1	GW	P	NENW		1	MVRD	P	UTU-38427	N2995
BONANZA FEDERAL 3-15	15	100S	230E	4304731278	8406		1	GW	P	NENW		1	MVRD	P	U-38428	N2995

★ not moved into unit

BONANZA 1023-15H	15	100S	230E	4304738316	16688		1	GW	P	SENE		1	MVRD	P	UTU-38427	N2995
BONANZA 1023-15J	15	100S	230E	4304738817	16988		1	GW	P	NWSE		1	MVRD	P	UTU-38427	N2995
BONANZA 1023-15H4CS	15	100S	230E	4304750741	17492		1	GW	P	NESE	D	1	MVRD	P	UTU 38427	N2995
BONANZA 1023-15I2AS	15	100S	230E	4304750742	17493		1	GW	P	NESE	D	1	WSMVD	P	UTU 38427	N2995
BONANZA 1023-15I4BS	15	100S	230E	4304750743	17490		1	GW	P	NESE	D	1	WSMVD	P	UTU 38427	N2995
BONANZA 1023-15P1BS	15	100S	230E	4304750744	17491		1	GW	P	NESE	D	1	WSMVD	P	UTU 38427	N2995
LOOKOUT POINT STATE 1-16	16	100S	230E	4304730544	1495		3	GW	P	NESE		3	WSMVD	P	ML-22186-A	N2995
BONANZA 1023-16J	16	100S	230E	4304737092	15987		3	GW	OPS	NWSE		3	WSMVD	OPS	ML-22186-A	N2995
BONANZA 1023-17B	17	100S	230E	4304735747	15165		1	GW	P	NWNE		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-17C	17	100S	230E	4304738237	16585		1	GW	P	NENW		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-17D3S	17	100S	230E	4304750511	17943		1	GW	P	NENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-17E2S	17	100S	230E	4304750512	17944		1	GW	P	NENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-17E3AS	17	100S	230E	4304750513	17945		1	GW	P	NENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-17E3CS	17	100S	230E	4304750514	17946		1	GW	P	NENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-18G	18	100S	230E	4304735621	14410		1	GW	P	SWNE		1	WSMVD	P	U-38241	N2995
BONANZA 1023-18B	18	100S	230E	4304735721	14395		1	GW	P	NWNE		1	WSMVD	P	U-38421	N2995
BONANZA 1023-18DX (RIGSKID)	18	100S	230E	4304736218	14668		1	GW	P	NWNW		1	WSMVD	P	U-38241	N2995
BONANZA 1023-18A	18	100S	230E	4304738243	16625		1	GW	P	NENE		1	WSMVD	P	UTU-38421	N2995
BONANZA 1023-18F	18	100S	230E	4304738244	16624		1	GW	P	SENW		1	WSMVD	P	UTU-38421	N2995
BONANZA 1023-18E	18	100S	230E	4304738245	16645		1	GW	P	SWNW		1	MVRD	P	UTU-38421	N2995
BONANZA 1023-18C	18	100S	230E	4304738246	16734		1	GW	P	NENW		1	MVRD	P	UTU-38421	N2995
BONANZA 1023-18G-1	18	100S	230E	4304738916	17135		1	GW	P	SWNE		1	WSMVD	P	UTU-38421	N2995
BONANZA 1023-18D3AS	18	100S	230E	4304750448	17498		1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18D3DS	18	100S	230E	4304750449	17499		1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18E2DS	18	100S	230E	4304750450	17497		1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18E3AS	18	100S	230E	4304750451	17496		1	GW	P	SENW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18L2S	18	100S	230E	4304750520	18111		1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18L3S	18	100S	230E	4304750521	18110		1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18K3AS	18	100S	230E	4304751061	18112		1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18K3BS	18	100S	230E	4304751063	18113		1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18M2AS	18	100S	230E	4304751064	18117		1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18M2DS	18	100S	230E	4304751065	18116		1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18N2AS	18	100S	230E	4304751066	18114		1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18N2DS	18	100S	230E	4304751067	18115		1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-10F	10	100S	230E	4304738225	16565			GW	P	SENW			MVRD	P	UTU 72028	N2995
BONANZA 1023-6D1AS	6	100S	230E	4304751450	18320			GW	P	NENW	D		WSMVD	P	UTU 38419	N2995
BONANZA 1023-6C1CS	6	100S	230E	4304751448	18319			GW		NENW	D				UTU 38419	N2995
BONANZA 1023-6D3AS	6	100S	230E	4304751452	18317			GW	P	NENW	D		WSMVD	P	UTU 38419	N2995

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-37355
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: PONDEROSA
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: BONANZA 1023-8H
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2619 FNL 0799 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 08 Township: 10.0S Range: 23.0E Meridian: S		9. API NUMBER: 43047382220000
PHONE NUMBER: 720 929-6507		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 3/24/2016	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> CHANGE WELL NAME	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input checked="" type="checkbox"/> OTHER	
	OTHER: <input type="text" value="TUBING FAILURE"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. <div style="display: flex; justify-content: space-between;"> <div style="width: 60%;"> A WORKOVER FOR TUBING FAILURE HAS BEEN COMPLETED ON THE BONANZA 1023-8H WELL. PLEASE SEE THE ATTACHED OPERATIONS SUMMARY REPORT FOR DETAILS. </div> <div style="width: 35%; text-align: right;"> Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY April 05, 2016 </div> </div>		
NAME (PLEASE PRINT) Jennifer Thomas	PHONE NUMBER 720 929-6808	TITLE Regulatory Specialist
SIGNATURE N/A	DATE 4/4/2016	

US ROCKIES REGION
Operation Summary Report

Well: BONANZA 1023-8H				Spud date: 10/21/2007				
Project: UTAH-UINTAH			Site: BONANZA 1023-8H PAD				Rig name no.: ROCKY MOUNTAIN WELL SERVICE 1/1	
Event: WELL WORK EXPENSE			Start date: 3/15/2016				End date: 3/17/2016	
Active datum: RKB @5,302.99usft (above Mean Sea Level)				UWI: BONANZA 1023-8H				
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation
3/15/2016	6:45 - 7:00	0.25	MAINT	48		P		HSM
	7:00 - 9:30	2.50	MAINT	30	G	P		RD RIG. ROAD RIG F/ BON 1023-9H2BS. MIRU RIG & SPOT EQUIP.
	9:30 - 12:30	3.00	MAINT	31	I	P		SICP = 800 PSI. BLW WELL DOWN T/ FBT FOR 30 MIN. PUMP 20 BBLS DOWN TBG. ND WH, NU BOP. RU RIG FLOOR & TBG EQUIP. PUMP 20 BBLS DOWN CSG. UNLAND TBG (TBG NOT STUCK) LD 4 1/16 TBG HNGR. PREP & TALLY NEW 2 3/8 L-80 TBG. PU RIH W/ 19 JTS. TAG FILL @ 7917'. XOVER TBG EQUIP. POOH STD BACK 19 JTS.
	12:30 - 17:00	4.50	MAINT	45	A	P		MIRU DELSCO TBG SCANNERS. POOH W/ 233 JTS 2 3/8 J-55. FOUND: 77 YB, 13 BB, 3 DBB, 140 RB. HEAVY PITTING ON PIN END OF RED BAND JTS. LIGHT OD SCALE STARTED @ JT 125-165. HEAVY OD SCALE STARTED @ JT 166 - 204. LIGHT T/ NO SCALE @ JT 205 - 233'. HOLE IN JT 225, 6" ABOVE PIN END. LD OLD POBS. SWI. RDMO DELSCO TBG SCANNERS. SDFN.
3/16/2016	6:45 - 7:00	0.25	MAINT	48		P		HSM.
	7:00 - 15:00	8.00	MAINT	31	I	P		SICP = 730 PSI. BLW WELL DWN. PUMP 20 BBLS T/ CONT WELL. PU 3 7/8 MILL, POBS & 1.875 XN. PREP & TALLY YB 2 3/8 J-55 TBG. PU & RIH W/ 248 JTS, TAG @ 7905'. LD 8 JTS EOT @ 7714'. RU DRL EQUIP. SWIFN.
3/17/2016	6:45 - 7:00	0.25	MAINT	48		P		HSM
	7:00 - 11:30	4.50	MAINT	44	D	P		SICP = 630 PSI. BLW WELL DWN T/ FBT. RU WTF FU/N2 UNIT'S. BRK CONV CIRC (1hr 30min T/ GET RETURNS) MILL DWN F/ 7905' - 7960'. STOP MAKING HOLE @ 7960' (OLD POBS). CIRC WELL CLN. PUMP 5 BBLS T-MAC T/ CONT TBG. RD DRL EQUIP.
	11:30 - 13:30	2.00	MAINT	31	I	P		POOH LD 19 JTS 2 3/8 J-55. STD BCK 231 JTS. LD XN, POBS & 3 7/8 MILL.

US ROCKIES REGION

Operation Summary Report

Well: BONANZA 1023-8H

Spud date: 10/21/2007

Project: UTAH-UINTAH

Site: BONANZA 1023-8H PAD

Rig name no.: ROCKY MOUNTAIN WELL SERVICE
1/1

Event: WELL WORK EXPENSE

Start date: 3/15/2016

End date: 3/17/2016

Active datum: RKB @5,302.99usft (above Mean Sea
Level)

UWI: BONANZA 1023-8H

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation
	13:30 - 17:00	3.50	MAINT	31	I	P		PU 1.875 XN/NC. RIH W/ 231 JTS 2 3/8 J-55. RU BROACH EQUIP. BROACH T/ XN @ 7975'. RD BROACH EQUIP. PU 4 1/16 WTF HNGR. LAND TBG ON HNGR. EOT @ 7975'. RD TBG EQUIP & RIG FLOOR. ND BOP, NU WH. SWIFWE. RACK OUT RIG EQUIP. SDFWE.
3/23/2016	7:00 - 17:00	10.00	PROD	42		P		SWABBING FL 4400, 1 RUN, 27 BARRELS
3/24/2016	7:00 - 12:00	5.00	MAINT	35		P		WELL NAME: Bonanza 1023-8H Job Code: 80012176 WINS #: ZID: CTS953 FOREMAN: V1-Ryan Kunkel MECHANICAL: Craig Massey SLICKLINE COMPANY JDM SLICKLINE OPERATOR Cade Goodridge TEL.NUMBER: 435-828-0593 3/24/2016 Ex. mm/dd/yy JOB DESCRIPTION Pulled scale knocker from seat nipple @ 7375'. RIH scratcher through seat nipple to TD @ 7951'. Broach 1.90" to seat nipple. Drop and chase chemical sticks. Set new PCS standard bumper spring. Drop new venturi plunger. RTP. TP=490, CP=640, FL=4600'. FLUID LEVEL 4600 SEAT NIPPLE DEPTH 7315 SN TYPE X TD (Max Depth) 7951